

INDEX OF SHEETS


SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX, HIGHWAY STANDARDS, AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	LOCATION MAP
5-15	ROADWAY PLAN
16	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT (BD24)
17	DETAILS FOR DEPRESSED CURB AND GUTTER AND SHOULDER TREATMENT AT TBT TY 1 SPL (BD34)
18	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC 10)
19	ARTERIAL ROAD INFORMATION SIGNING (TC22)

HIGHWAY STANDARDS

STD. NO.	TITLE
630001 - 10	STEEL PLATE BEAM GUARDRAIL
630101 - 09	GUARDRAIL MOUNTED ON EXISTING CULVERTS
630201 - 06	PCC/HMA STABILIZATION AT STEEL PLATE BEAM GUARDRAIL
630301 - 05	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631011 - 08	TRAFFIC BARRIER TERMINAL, TYPE 2
631031 - 10	TRAFFIC BARRIER TERMINAL, TYPE 8
635006 - 03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011 - 02	REFLECTOR MARKER AND MOUNTING DETAILS
701008 - 03	OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24' (600 mm) FROM PAVEMENT EDGE
701101 - 02	OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5 m) TO 24' (600 mm) FROM PAVEMENT EDGE
701301 - 04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701326 - 04	LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS ≥ 45 MPH
701422 - 04	LANE CLOSURE, MULTILANE, FOR SPEEDS ≥ 45 MPH TO 55 MPH
701901 - 02	TRAFFIC CONTROL DEVICES

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT 800-892-0123 OR "CUAN" (CHICAGO UTILITY ALERT NETWORK), 312-744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES (48 HOUR NOTIFICATION IS REQUIRED).
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND LOCAL AGENCIES.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM 72 HOURS IN ADVANCE OF BEGINNING WORK.
- WHEN GUARDRAIL POSTS ARE PLACED BEHIND CONCRETE HEADWALLS, THE POSTS SHALL NOT BE PLACED TO BLOCK THE DRAINAGE OPENING.
- THE CONTRACTOR SHALL ONLY PERFORM WORK ON ONE SIDE OF THE ROAD AT ANY TIME.
- THE CONTRACTOR SHALL SUSPEND GUARDRAIL REMOVAL OPERATIONS WHENEVER THE AMOUNT OF REMOVED GUARDRAIL EXCEEDS TWO DAYS PRODUCTION TO REPLACE THE GUARDRAIL.



USER NAME = .USER.	DESIGNED - EF	REVISED -
	DRAWN - EF	REVISED -
PLOT SCALE = 100.0000 "/ IN.	CHECKED - RS	REVISED -
PLOT DATE = 3/19/2012	DATE - 03/22/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GUARDRAIL IMPROVEMENTS - KANE COUNTY
INDEX OF SHEETS, HIGHWAY STANDARDS, AND GENERAL NOTES

SCALE: 50 SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2011-025-GRR	KANE	19	2
*	VARIOUS ROUTES			

CONTRACT NO. 60P25
ILLINOIS FED. AID PROJECT