

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FED 20% STATE	
				ROADWAY	
				0031	URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,147	1,147	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	791	791	
20101000	TEMPORARY FENCE	FOOT	1,180	1,180	
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	2	2	
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	2	2	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10	10	
28000305	TEMPORARY DITCH CHECKS	FOOT	95	95	
28000400	PERIMETER EROSION BARRIER	FOOT	3,762	3,762	
28000500	INLET AND PIPE PROTECTION	EACH	9	9	
28000510	INLET FILTERS	EACH	112	112	
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	471	471	
67100100	MOBILIZATION	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
X2010300	TREE REMOVAL (UNDER 6 UNITS DIAMETER)	UNIT	553	553	

\* SPECIALTY ITEM

FILE NAME :	USER NAME : RUSERT	DESIGNED : CEO	REVISED : 04-06-2012	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
FILE NO. :		DRAWN : KES	REVISED : -			338	2011-037-DTR	DUPAGE	4	138	
		CHECKED : PJO	REVISED : -			CONTRACT NO. 60P43					
		DATE : 03-22-2012	REVISED : -			ILLINOIS FED. AID PROJECT					
					SCALE: AS SHOWN	SHEET NO. 1 OF 2 SHEETS		STA.	TO STA.		