



BASCULE FRAMING PLAN

Notes (Sheets S5 and S6):

1. Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.
2. The details shown are the final configurations and details. The Contractor shall be responsible for obtaining approval for all methods and procedures necessary to achieve the details shown.
3. The Contractor shall verify all pertinent dimensions prior to fabrication.
4. Where removal of existing rivets is required to facilitate the work, remove rivets and replace with the same diameter high strength bolts, unless noted otherwise.
5. See Sheet S2 for notes regarding painting of new and existing steel.
6. The Contractor shall mill ends of angles and plates as required to allow for proper installation. Cost included in the Pay Item for Structural Steel Repair.
7. All bolts on Sheet S6 are 3/4"φ in 1 3/16"φ holes, unless noted otherwise.

FILE NAME =	USER NAME =	DESIGNED - JMS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>BASCULE FRAMING PLAN STRUCTURE NO. 099-0101</b>	F.A.P. RTE. 607	SECTION 2011-065-BR	COUNTY WILL	TOTAL SHEETS 33	SHEET NO. 12	
		CHECKED - JMH	REVISED -			CONTRACT NO. 60P84					
		DRAWN - PRH	REVISED -			ILLINOIS FED. AID PROJECT					
		CHECKED - JMH	REVISED -			SHEET NO. S5 OF S6 SHEETS					