

**SUMMARY OF QUANTITIES**

LS3EL LS3EL LS3EL LS3EL 07POL 07POL

**CONSTRUCTION TYPE CODE**

VHE = VILLAGE OF HOFFMAN ESTATES  
VED = VILLAGE OF EAST DUNDEE

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				ROADWAY BEVERLY RD	BEVERLY RD TRAFFIC SIGNAL	ROCK RD DR TRAFFIC SIGNAL	INTERCONNECT	BEVERLY RD LIGHTING	EMERGENCY VEHICLE PRE-EMPTION (EVP) DEVICE
				COOK	COOK	KANE	COOK	COOK	COOK
				90% FED 10% STATE	90% FED 6.67% STATE 3.33% VHE	90% FED 6.67% STATE 3.33% VED	90% FED 10% STATE	100% VHE	100% VHE
				0005	0021 .01	0021	0021 .02	0021 .01	0021 .02
20200100	EARTH EXCAVATION	CU YD	793	793					
20800150	TRENCH BACKFILL	CU YD	12	12					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	2862	2862					
21400100	GRADING AND SHAPING DITCHES	FOOT	392	392					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3.9	3.9					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3.9	3.9					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3.9	3.9					
25200110	SODDING, SALT TOLERANT	SO YD	2862	2862					
28000305	TEMPORARY DITCH CHECKS	FOOT	125	125					
28000400	PERIMETER EROSION BARRIER	FOOT	1367	1367					
28000510	INLET FILTERS	EACH	25	25					
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	1394	1394					
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SO YD	438	438					
35501314	HOT-MIX ASPHALT BASE COURSE, 7 1/2"	SO YD	816	816					
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	2.4	2.4					
40600300	AGGREGATE (PRIME COAT)	TON	12	12					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	9	9					
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	36	36					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SO YD	61	61					
40600985	CONCRETE SURFACE REMOVAL-BUTT JOINT	SO YD	429	429					
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N90	TON	103	103					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	676	676					
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SO YD	438	438					
42001300	PROTECTIVE COAT	SO YD	751	751					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	76	-	38	38			
44000100	PAVEMENT REMOVAL	SO YD	29	29					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	4462	4462					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1030	1030					

URBAN

FILE NAME: p:\2009\m090806.vor\p\l\cadd\W038\_IL72\_Beverly\Shets\03-0168P98-ht-500.dgn  
 PLOT SCALE: 2.0000 / IN.  
 PLOT DATE: 4/6/2012  
 MILLENNIA PROFESSIONAL SERVICES

SPECIALTY ITEM *Rev.*



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.795.8118 voice, 630.839.2566 fax  
 www.mps-ll.com  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 4/6/2012	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**IL 72 - HIGGINS RD  
 AT BEVERLY RD AND AT ROCK ROAD DR**

**SUMMARY OF QUANTITIES**

F.A.P. RTE. 341	SECTION 2011-071-N	COUNTY COOK/KANE	TOTAL SHEETS 56	SHEET NO. 3
CONTRACT NO. 60P90			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

SCALE: SHEET NO. OF SHEETS STA. TO STA.

p:\2009\m090806.vor\p\l\cadd\W038\_IL72\_Beverly\Shets\03-0168P98-ht-500.dgn