

SUMMARY OF QUANTITIES


CONSTRUCTION TYPE CODE

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				ROADWAY BEVERLY RD	BEVERLY RD TRAFFIC SIGNAL	ROCK RD DR TRAFFIC SIGNAL	INTERCONNECT	BEVERLY RD LIGHTING	EMERGENCY VEHICLE PRE-EMPTION (EVP) DEVICE
				COOK 90% FED 10% STATE	COOK 90% FED 6.67% STATE 3.33% VHE	KANE 90% FED 6.67% STATE 3.33% VED	COOK 90% FED 10% STATE	COOK 100% VHE	COOK 100% VHE
				0005	0021	0021	0021	0021	0021
81603050	UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA <i>POLYETHYLENE</i>	FOOT	2550					2550	
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	12					12	
82500330	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 60AMP	EACH	1					1	
83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	12					12	
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	108					108	
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	12					12	
84200804	REMOVAL OF POLE FOUNDATION	EACH	3					3	
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3					3	
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1				
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	3034		3034				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	1587		1587				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	5112		5112				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	529		529				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4851		4851				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	96		96				
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1		1				
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1		1				
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1		1				
87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1		1				
87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1		1				
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1		1				
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8		8				
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4				
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10		10				
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	35		35				
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	12		8	4			
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	5		2	3			
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		-	1			

VHE = VILLAGE OF HOFFMAN ESTATES
VED = VILLAGE OF EAST DUNDEE

• SPECIALTY ITEM

FILE NAME : p:\2009\m09006\server\phi\1\cadd\W038_IL72_Beverly\Shs\03-0168P90-sh1-500.dgn
PLOT SCALE : 2.0000 7 IN.
USER NAME : Millenna Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
630.705.0110 voice, 630.839.2566 fax
www.mps-ill.com

MILLENNIA PROFESSIONAL SERVICES

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 4/6/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 72 - HIGGINS RD
AT BEVERLY RD AND AT ROCK ROAD DR

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 341	SECTION 2011-071-N	COUNTY COOK/KANE	TOTAL SHEETS 56	SHEET NO. 6
CONTRACT NO. 60P90				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

p:\2009\m09006\server\phi\1\cadd\W038_IL72_Beverly\Shs\03-0168P90-sh1-500.dgn