

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

VHE = VILLAGE OF HOFFMAN ESTATES
VED = VILLAGE OF EAST DUNDEE

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				ROADWAY BEVERLY RD	BEVERLY RD TRAFFIC SIGNAL	ROCK RD DR TRAFFIC SIGNAL	INTERCONNECT	BEVERLY RD LIGHTING	EMERGENCY VEHICLE PRE-EMPTION (EVP) DEVICE
				COOK	COOK	KANE	COOK	COOK	COOK
				90% FED 10% STATE	90% FED 6.67% STATE 3.33% VHE	90% FED 6.67% STATE 3.33% VED	90% FED 10% STATE	100% VHE	100% VHE
				0005	0021	0021	0021	0021	0021
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2		2				
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1			1			
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3-SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1			1			
88030310	SIGNAL HEAD, LED, 3-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1				
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2		2				
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	14		10	4			
88500100	INDUCTIVE LOOP DETECTOR	EACH	8		8				
88600100	DETECTOR LOOP, TYPE 1	FOOT	496		496				
88600700	PREFORMED DETECTOR LOOP	FOOT	129		129				
88700200	LIGHT DETECTOR	EACH	3						3
88700300	LIGHT DETECTOR AMPLIFIER	EACH	3						3
88800100	PEDESTRIAN PUSH-BUTTON	EACH	2		2				
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1				
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2144				2144		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1				
89502380	REMOVE EXISTING HANDHOLE	EACH	2		2				
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5		5				
X0323927	MAINTENANCE OF LIGHTING SYSTEM	EACH	1					1	
X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	1170						1170
Δ X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	132	132					
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1					
* X8360110	LIGHT POLE FOUNDATION, SPECIAL	FOOT	27					27	
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1				
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	2		1	1			
X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	2144				2144		
X8950305	REMOVE EXISTING SIGNAL HEAD	EACH	12			12			
Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	11	11					
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	78	78					

Δ Non-participating (100% State) STASL

• SPECIALTY ITEM

FILE NAME = p:\2009\m09086-ver-ver-phs\cadd\W038-IL72-Beverly\Shts\03-0168P98-sht-500.dgn
PLOT SCALE = 2.0000 / IN.
USER NAME = Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
630.705.9119 voice, 630.839.2566 fax
www.mps-ill.com
MILLENNIA PROFESSIONAL SERVICES

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 4/6/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 72 - HIGGINS RD
AT BEVERLY RD AND AT ROCK ROAD DR
SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 341	SECTION 2011-071-N	COUNTY COOK/KANE	TOTAL SHEETS 56	SHEET NO. 7
CONTRACT NO. 60P90			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

p:\2009\m09086-ver-ver-phs\cadd\W038-IL72-Beverly\Shts\03-0168P98-sht-500.dgn