

SUMMARY OF QUANTITIES				CONSTRUCTION CODE								
				GOLF ROAD AT LAWLER AVENUE	GOLF ROAD AT LAVERGNE AVENUE	GROSS POINT ROAD AT CHURCH STREET	U.S. RTE 41 (SKOKIE BOULEVARD) AT CHURCH STREET	U.S. RTE 41 (SKOKIE BOULEVARD) AT GROSS POINT ROAD	INTERCONNECT	LIGHTING - GROSS POINT ROAD AT CHURCH STREET	LIGHTING - U.S. RTE 41 (SKOKIE BOULEVARD) AT GROSS POINT ROAD	
				90% FEDERAL 5% STATE 5% VILLAGE OF SKOKIE	90% FEDERAL 5% STATE 5% VILLAGE OF SKOKIE	90% FEDERAL 5% STATE 5% VILLAGE OF SKOKIE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% VILLAGE OF SKOKIE	90% FEDERAL 10% VILLAGE OF SKOKIE	
				TRAFFIC SIGNALS 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	INTERCONNECT 0021 URBAN	LIGHTING 0021 URBAN	LIGHTING 0021 URBAN	
CODE NO.	ITEM	UNIT	TOTAL									
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3,627							3,627		
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	5,793	803	836	1,361	1,060	1,733				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	8,500	1,270	1,417	1,768	1,380	2,665				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	8,658	2,016	1,568	1,750	1,602	1,722				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	6,017	400	1,048	1,621	652	2,296				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	12,612	1,350	2,051	2,647	2,296	4,268				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	569	117	159	111	100	82				
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	3		1			2				
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	3		1			2				
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	12	4		4	2	2				
87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	2				2					
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	2	1	1							
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1	1								
87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1				1					
87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	2	1			1					
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	2	1		1						
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1					1				
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	2		2							
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1					1				
87702300	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 24 FT. AND 34 FT.	EACH	1		1							
87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	3			2		1				

* 100% OF THE COST SHALL BE PAID BY VILLAGE OF SKOKIE (07POL, 01, 0021) ** SPECIALTY ITEM

FILE NAME = 4085.877-TR1.dwg

USER NAME = ZACH WALLSTEN	DESIGNED - JRD	REVISED -
PLOT SCALE = 1" = .0833'	DRAWN - ZCW	REVISED -
PLOT DATE = 3/22/2012	CHECKED - KLB	REVISED -
	DATE - 3/22/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
(SHEET 3 OF 5)**

SCALE N.A. SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VARIES	2011-209-TS	COOK	52	5
ILLINOIS FED. AID PROJECT			CONTRACT # 60R47	