

INDEX OF SHEETS

1. TITLE SHEET
2. INDEX OF SHEETS, GENERAL NOTES, AND STATE STANDARDS
- 3.-4. SUMMARY OF QUANTITIES
- 5.-10. DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS
11. TEMPORARY TRAFFIC SIGNAL INSTALLATION AND REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT - ILL ROUTE 58 (GOLF ROAD) AT DEE ROAD
12. TEMPORARY CABLE PLAN, TEMPORARY PHASE DESIGNATION DIAGRAM, AND TEMPORARY EMERGENCY VEHICLE PREEMPTION SEQUENCE - ILL ROUTE 58 (GOLF ROAD) AT DEE
13. TRAFFIC SIGNAL MODERNIZATION PLAN - ILL ROUTE 58 (GOLF ROAD) AT DEE ROAD
14. SCHEDULE OF QUANTITIES, CABLE PLAN, PHASE DESIGNATION DIAGRAM, AND EMERGENCY VEHICLE PREEMPTION SEQUENCE - ILL ROUTE 58 (GOLF ROAD) AT DEE
15. TEMPORARY TRAFFIC SIGNAL INSTALLATION AND REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT - ILL ROUTE 58 (GOLF ROAD) AT WESTERN AVENUE
16. TEMPORARY CABLE PLAN, TEMPORARY PHASE DESIGNATION DIAGRAM, AND TEMPORARY EMERGENCY VEHICLE PREEMPTION SEQUENCE - ILL ROUTE 58 (GOLF ROAD) AT
17. TRAFFIC SIGNAL MODERNIZATION PLAN - ILL ROUTE 58 (GOLF ROAD) AT WESTERN
18. SCHEDULE OF QUANTITIES, CABLE PLAN, PHASE DESIGNATION DIAGRAM, AND EMERGENCY VEHICLE PREEMPTION SEQUENCE - ILL ROUTE 58 (GOLF ROAD) AT
19. TEMPORARY INTERCONNECT PLAN AND TEMPORARY INTERCONNECT SCHEMATIC - ILL ROUTE 58 (GOLF ROAD) FROM POTTER ROAD TO GREENWOOD AVENUE
20. INTERCONNECT PLAN - ILL ROUTE 58 (GOLF ROAD) FROM POTTER ROAD TO GREENWOOD AVENUE - IDOT SYSTEM 11
21. INTERCONNECT SCHEMATIC - IDOT SYSTEM 11 & 12
22. DISTRICT ONE STANDARD MAST ARM MOUNTED STREET NAME SIGNS
- 23.-25. DISTRICT ONE STANDARD DETAILS (TC-10, TC-14, & TC-22)
26. DISTRICT ONE TYPICAL PAVEMENT MARKINGS

GENERAL NOTES

THE ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", JANUARY 1, 2012; MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, LATEST EDITION; PROJECT SPECIFICATIONS; ALL APPLICABLE REQUIREMENTS OF THE DUPAGE COUNTY DIVISION OF TRANSPORTATION; THE VILLAGE OF GLEN ELLYN; THE CITY OF WHEATON; THE VILLAGE OF CAROL STREAM; THE VILLAGE OF GLENDALE HEIGHTS; THE VILLAGE OF BLOOMINGDALE; ALL APPLICABLE REQUIREMENTS OF THE ORDINANCES OF AUTHORITIES HAVING JURISDICTION; AND ALL ADDENDA THERETO SHALL GOVERN THIS WORK.

THE STANDARD SPECIFICATIONS, PROJECT SPECIFICATIONS, CONSTRUCTION PLANS, AND SUBSEQUENT DETAILS ARE ALL TO BE CONSIDERED AS PART OF THE CONTRACT. INCIDENTAL ITEMS OR ACCESSORIES NECESSARY TO COMPLETE THIS WORK MAY NOT BE SPECIFICALLY NOTED BUT ARE TO BE CONSIDERED A PART OF THE CONTRACT.

WHENEVER, DURING CONSTRUCTION OPERATIONS, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES, ETC. SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THE LOOSE MATERIAL WILL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR'S FAILURE TO PROVIDE THE ABOVE WILL PRECLUDE ANY POSSIBLE ADDED COMPENSATION REQUESTED DUE TO DELAYS OF UNSTABLE MATERIALS CREATED AS A RESULT THEREOF.

THE CONTRACTOR SHALL SOLELY BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ADEQUATE SIGNS, TRAFFIC CONTROL DEVICES, AND WARNING DEVICES TO INFORM AND PROTECT THE PUBLIC DURING ALL PHASES OF CONSTRUCTION.

THE CONTRACTOR IS RESPONSIBLE FOR RETURNING ALL AREAS AFFECTED BY EQUIPMENT OR LABORERS TO EXISTING CONDITIONS. THE CONTRACTOR IS ALSO RESPONSIBLE FOR PROTECTING ALL NEW WORK UNTIL COMPLETION OF THIS CONTRACT.

EXISTING UTILITIES: WHEN THE PLANS OR SPECIAL PROVISIONS INCLUDE INFORMATION PERTAINING TO THE LOCATION OF UNDERGROUND UTILITY FACILITIES, SUCH INFORMATION REPRESENTS ONLY THE OPINION OF THE ENGINEER AS TO THE LOCATION OF SUCH UTILITIES AND IS ONLY INCLUDED FOR THE CONVENIENCE OF THE CONTRACTOR. THE ENGINEER AND OWNER ASSUME NO RESPONSIBILITY WHATSOEVER IN RESPECT TO THE SUFFICIENCY OR THE ACCURACY OF THE INFORMATION SHOWN ON THE PLANS RELATIVE TO THE LOCATION OF UNDERGROUND UTILITY FACILITIES OR THE MANNER IN WHICH THEY ARE TO BE REMOVED OR ADJUSTED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES. THE CONTRACTOR SHALL ALSO CONTACT J.U.L.I.E. TO OBTAIN LOCATES OF THE RESPECTIVE UTILITY COMPANIES UNDERGROUND FACILITIES.

CONTRACTOR IS RESPONSIBLE FOR CONTACTING J.U.L.I.E. AT 1-800-892-0123 AND MUST ACQUIRE A DIG NUMBER A MINIMUM OF 72 HOURS PRIOR TO ANY WORK BEING DONE

RESTORATION OF WORK AREA: RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC. AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD IN ACCORDANCE TO STANDARD SPECIFICATIONS ARTICLE 252 WHICH SHALL INCLUDE THE REQUIRED WATERING PER ARTICLE 252.08. ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDING IN ACCORDANCE WITH STANDARD SPECIFICATIONS ARTICLE 250 AND 251, RESPECTIVELY.

THE GENERAL CONTRACTOR IS REQUIRED TO HIRE AN ENVIRONMENTAL FIRM WITH AT LEAST FIVE (5) DOCUMENTED LEAKING UNDERGROUND STORAGE TANK CLEANUPS OR THAT IS PRE-QUALIFIED IN HAZARDOUS WASTE BY THE DEPARTMENT TO REMEDIATE THE SOIL CONTAMINATION AND MONITOR FOR WORKER PROTECTION.

IDOT STANDARDS

- 000001-04 STANDARD SYMBOLS, ABBREVIATIONS, & PATTERNS
- 1006 DECIMAL OF AN INCH OF A FOOT
- 442101-07 CLASS B PATCHES
- 424001-06 PERPENDICULAR CURB RAMPS FOR SIDEWALK
- 424006 DIAGONAL CURB RAMPS FOR SIDEWALK
- 424011 CORNER PARALLEL CURB RAMPS FOR SIDEWALK
- 424021 DEPRESSED CORNER FOR SIDEWALKS
- 606306-03 CORRUGATED PC CONCRETE MEDIANS
- 701001-02 OFF-ROAD OPERATIONS 2L, 2W, >15' AWAY
- 701006-03 OFF-ROAD OPERATIONS 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
- 701011-02 OFF-ROAD OPERATIONS 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
- 701301-04 LANE CLOSURE 2L, 2W, SHORT TIME OPERATIONS
- 701501-06 URBAN LANE CLOSURE 2L, 2W UNDIVIDED
- 701808-03 URBAN LANE CLOSURE MULTILANE 2W WITH MOUNTABLE MEDIAN
- 701701-03 URBAN LANE CLOSURE MULTILANE INTERSECTION
- 701801-05 LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
- 701901-02 TRAFFIC CONTROL DEVICES
- 720001-01 SIGN PANEL MOUNTING DETAIL
- 720006-03 SIGN PANEL ERECTION DETAIL
- 780001-03 TYPICAL PAVEMENT MARKINGS
- 814001-02 HANDHOLE
- 814008-02 DOUBLE HANDHOLES
- 857001-01 STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES
- 862001-01 UNINTERRUPTIBLE POWER SUPPLY (UPS)
- 873001-02 TRAFFIC SIGNAL GROUNDING & BONDING
- 877001-05 STEEL MAST ARM ASSEMBLY AND POLE, 16' THROUGH 55'
- 878001-09 CONCRETE FOUNDATION DETAILS
- 880001-01 SPAN WIRE MOUNTED SIGNALS AND FLASHING BEACON INSTALLATION
- 880008-01 TRAFFIC SIGNAL MOUNTING DETAILS
- 886001-01 DETECTOR LOOP INSTALLATIONS

FILE NAME = 4085.879-TR1.dwg	USER NAME = ZACH WALLSTEN	DESIGNED - JRD	REVISED -	<p align="center">STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</p>	<p align="center">INDEX OF SHEETS, GENERAL NOTES, & IDOT STANDARDS - ILL RTE 58 (GOLF RD) F.A.P. 339 AT DEE RD & WESTERN AVE</p>	F.A.P. RTE. 339	SECTION 2011-211-TS	COUNTY COOK	TOTAL SHEETS 26	SHEET NO. 2
PLOT SCALE = 1" = .0833'	CHECKED - KLB	REVISED -	SCALE N.A.			SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT # 60R51		ILLINOIS FED. AID PROJECT
PLOT DATE = 2/1/2012	DATE - 2/1/2012	REVISED -	GHA #4085.879							