

SUMMARY OF QUANTITIES				URBAN	CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES				URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005							CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	370	370							42001300	PROTECTIVE COAT	SO YD	245	245						
25200110	SODDING, SALT TOLERANT	SO YD	370	370							42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	135	135						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	54	54							42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1100	1100						
40600300	AGGREGATE (PRIME COAT)	TON	267	267							44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	61392	61392						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	93	93							44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	135	135						
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	2716	2716							44000600	SIDEWALK REMOVAL	SO FT	1100	1100						
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	771	771						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1031	1031							44022029	PARTIAL DEPTH REMOVAL 3"	SO YD	300	300						
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	667	667							44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	130	130						
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	130	130							44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	440	440						
40603085	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N70	TON	51	51							44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	565	565						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5568	5568							60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	4	4						
											60266600	VALVE BOXES TO BE ADJUSTED	EACH	2	2						
											60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	22	22						

FILE NAME =	USER NAME = rodriguezmo	DESIGNED -	REVISED -
c:\aw_work\privat\rodriguezmo\029379\0127312-stp-schedule.dwg		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**CHURCH ST. (GROSS POINT RD. TO DODGE AVE.)
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1313	(99B&0808)RS-1	COOK	30	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60R99	