

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	SUMMARY OF PATCHING
5-7	PROJECT STAGING MAPS
8	DETOUR PLAN (I-94 NB TO US 6 EB)
9-81	ROADWAY AND SUGGESTED MAINTENANCE OF TRAFFIC PLANS
82A-B	4-LANE CRC PAVEMENT WITH LUG SYSTEM (SD-04-41 FOR INFORMATIONAL USE ONLY)
83	FREEWAY ENTRANCE AND EXIT RAMP CLOSURE DETAILS (TC-08)
84	FREEWAY SINGLE AND MULTI-LANE WEAVE (TC-09)
85	TYPICAL APPLICATIONS: RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) (TC-11)
86-87	MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS (TC-12)
88	TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC-17)
89	DETOUR SIGNING FOR CLOSING STATE HIGHWAYS (TC-21)
90	TEMPORARY INFORMATION SIGNING (TC-22)
91	TRAFFIC CONTROL DETAILS FOR FREEWAY CENTER LANE CLOSURE SHOULDER LANE (TC-25)

STATE STANDARDS

STANDARD NO.	DESCRIPTION
000001-06	TYPICAL SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
420001-07	PAVEMENT JOINTS
420701-02	PAVEMENT FABRIC
442001-04	CLASS A PATCHES
442101-07	CLASS B PATCHES
701400-05	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-06	LANE CLOSURE, FREEWAY/EXPRESSWAY
701411-08	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP
701426-04	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER. FOR SPEEDS >= 45 MPH
701446-03	TWO LANE CLOSURE FREEWAY/EXPRESSWAY
701901-02	TRAFFIC CONTROL DEVICES
780001	TYPICAL PAVEMENT MARKING

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED).

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE (OR TOLLWAY) PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT (OR ISTHA).

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.

BEFORE BEGINING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKINGS LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

ALL PAVEMENT PATCHING LOCATIONS AND SIZES WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE ENGINEER SHALL CONTACT PATRICE HARRIS, AREA TRAFFIC FIELD ENGINEER AT (708) 597-9800 MINIMUM OF TWO (2) WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

THE MINIMUM CLASS A PATCH DIMENSIONS SHALL BE THE A LENGTH OF 4.5 FEET AND A WIDTH THAT INCLUDES HALF THE WIDTH OF THE TRAVEL WAY. THE MINIMUM CLASS B PATCH DIMENSIONS SHALL BE A LENGTH OF 6 FEET AND A WIDTH THAT INCLUDES THE FULL WIDTH OF THE TRAVEL WAY.

FOR ALL PATCHING LOCATIONS (MAINLINE AND RAMPS), CLASS PP-2 OR HIGHER CONCRETE IS TO BE USED.

THE ENGINEER SHALL FIELD VERIFY ALL CRACK AND JOINT SEALING LOCATIONS AND IDENTIFY ANY ADDITIONAL LOCATIONS DURING CONSTRUCTION.

PAVEMENT MARKING TAPE, TYPE III SHALL BE USED FOR TEMPORARY PAVEMENT MARKINGS.

FOR WORK OUTSIDE THE LIMITS OF BRIDGE APPROACH PAVEMENT, ALL REFERENCES IN THE HIGHWAY STANDARDS AND STANDARD SPECIFICATIONS FOR REINFORCEMENT, DOWEL BARS AND TIE BARS IN PAVEMENT, SHOULDERS, CURB, GUTTER, COMBINATION CURB AND GUTTER AND MEDIAN, AND CHAIR SUPPORTS FOR CRC PAVEMENT, SHALL BE EPOXY COATED, UNLESS NOTED ON THE PLANS.

THE COST TO FURNISH AND INSTALL TEMPORARY DETOUR SIGNS FOR THE NB I-94 TO EB US 6 RAMP CLOSURE AS SHOWN IN THE PLANS SHALL BE INCLUDED IN THE COST OF "TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)".

INDIANA NOTES

THE CONTRACTOR SHALL CONTACT SKIP CLAUSSEN OF THE STATE OF INDIANA'S GARY TRAFFIC MANAGEMENT CENTER (TMC) AT (219) 939-3650 A MINIMUM OF 1 WEEK PRIOR TO ANY SHOULDER OR LANE CLOSURES THAT FALL WITHIN THE STATE OF INDIANA.

THE CONTRACTOR SHALL CONTACT MIKE YACULLO OF THE LAPORTE DISTRICT OFFICE AT (219) 325-7555 FOR APPROVAL TO BEGIN WORK WITHIN THE STATE OF INDIANA.

FILE NAME =	USER NAME = lloydjm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cf:\pwwork\pwwork\lloydjm\d0298297\013302-shr-plan.dgn	DRAWN -	REVISED -	80/94			2012-002CRC-PP	COOK	91	2	
PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -	CONTRACT NO. 60T34							
PLOT DATE = 4/4/2012	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
						SCALE:	SHEET	OF	SHEETS	STA. TO STA.