


FILE NAME = S:\JOL\6380-6399\6346\035\Micro\CADD Sheets\01688931-ht-500.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE
				100% STATE
				DRAINAGE
				0044
				URBAN
• 28000500	INLET AND PIPE PROTECTION	EACH	3	3
• 28000510	INLET FILTERS	EACH	13	13
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SO YD	448	448
35800100	PREPARATION OF BASE	SO YD	2,438	2,438
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	509	509
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	60	60
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	226	226
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	234	234
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	127	127
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	232	232
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	374	374
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,161	1,161
54213655	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 10"	EACH	1	1

• SPECIALTY ITEM

Rev.



USER NAME = dennisw	DESIGNED - TJS	REVISED -
PLOT SCALE = 20.0000' / 1"	DRAWN - DJW	REVISED -
PLOT DATE = 4/2/2012	CHECKED - MAG	REVISED -
	DATE - 4-2-12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**I-55 NORTHBOUND EXIT RAMP
SUMMARY OF QUANTITIES**

SCALE: N/A SHEET 2 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	112-636T	COOK	36	5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60T37	