

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				FUNDS		
				100% STATE	100% STATE	100% STATE
				ROADWAY 0005 URBAN	SAFETY 0021 URBAN	DRAINAGE 0044 URBAN
20800150	TRENCH BACKFILL	CU YD	1033			1033
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	3872			3872
21400100	GRADING AND SHAPING DITCHES	FOOT	570			570
25000210	SEEDING, CLASS 2A	ACRE	0.8			0.8
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72			72
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72			72
25100115	MULCH, METHOD 2	ACRE	0.8			0.8
25200110	SODDING, SALT TOLERANT	SO YD	940	940		
28000305	TEMPORARY DITCH CHECKS	FOOT	20			20
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13479	13479		
40600300	AGGREGATE (PRIME COAT)	TON	270	270		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	100	100		
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	930	930		
40600895	CONSTRUCTING TEST STRIP	EACH	3	3		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	334	334		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	747	747		

• SPECIALTY ITEM

FILE NAME =	DESIGNED - AAF	REVISED -
...\\D160138-sht-ADV-500-01.dgn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - JMM	REVISED -
PLOT DATE = 3/22/2012	DATE - 3/23/2012	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 1 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372	*	COOK	40	3
			CONTRACT NO. 60T38	
ILLINOIS FED. AID PROJECT				

*10102-683K, ETC&0507-635K/RS-1

Rev.