

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				FUNDS		
				100% STATE	100% STATE	100% STATE
				ROADWAY 0005 URBAN	SAFETY 0021 URBAN	DRAINAGE 0044 URBAN
40601005	HOT MIX ASPHALT REPLACEMENT OVER PATCHES	TON	84			84
40603085	HOT MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	817	817		
40603148	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	5882	5882		
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	5882	5882		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1250	1250		
42001300	PROTECTIVE COAT	SO YD	852	852		
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SO YD	51272	51272		
44002210	REMOVAL OVER PATCHES, 2 1/2" HOT-MIX ASPHALT	SO YD	667			667
44022029	PARTIAL DEPTH REMOVAL 3"	SO YD	4864	4864		
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	50	47		3
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	922	915		7
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	689	337		352
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	1604	1099		505
54247200	GRATING FOR CONCRETE FLARED END SECTION 54"	EACH	1			1

• SPECIALTY ITEM

FILE NAME :	DESIGNED - AAF	REVISED -
...D188T38-shr-ADV-500-02.dgn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - JMM	REVISED -
PLOT DATE = 3/22/2012	DATE - 3/23/2012	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 2 OF 5 SHEETS STA. TO STA.

*I0102-683K, ETC&0507-635KIRS-1

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372	*	COOK	40	4
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60T38	