

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				FUNDS		
				100% STATE	100% STATE	100% STATE
				ROADWAY 0005 URBAN	SAFETY 0021 URBAN	DRAINAGE 0044 URBAN
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1443			1443
60200105	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	42			42
60200305	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 3 FRAME AND GRATE	EACH	4			4
60201330	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 23 FRAME AND GRATE	EACH	12			12
60218300	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	5			5
60218400	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2			2
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10			10
66400105	CHAIN LINK FENCE, 4'	FOOT	12	12		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		
67100100	MOBILIZATION	LSUM	1	1		
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	LSUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LSUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	LSUM	1	1		
70102635	TRAFFIC CONTROL AND PROECTION, STANDARD 701701	LSUM	1	1		

• SPECIALTY ITEM

FILE NAME =	DESIGNED - AAF	REVISED -
...D160738-shc-ADV-500-03.dgn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - JMM	REVISED -
PLOT DATE = 3/22/2012	DATE - 3/23/2012	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 3 OF 5 SHEETS STA. TO STA.

*0102-683K, ETC&0507-635K)RS-1 *Rev.*

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372		COOK	40	5
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60T38	