

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN - 90 % FEDERAL, 10 % STATE		
				0004		0011
				STUENKEL ROAD	I-57	SN099-0526
20101000	TEMPORARY FENCE	FOOT	416	416		
20200100	EARTH EXCAVATION	CU YD	2230	2230		
20400800	FURNISHED EXCAVATION	CU YD	2420	2420		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	4006	4006		
25000210	SEEDING, CLASS 2A	ACRE	1.00	0.50	0.50	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90		
25100135	MULCH, METHOD 4	ACRE	0.50	0.50		
25100630	EROSION CONTROL BLANKET	SO YD	4006	4006		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	44	44		
28000305	TEMPORARY DITCH CHECKS	FOOT	40		40	
28200200	FILTER FABRIC	SO YD	1167			1167
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1

* SPECIALTY ITEM

TYLIN INTERNATIONAL	USER NAME * #USER#	DESIGNED - BES	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STUENKEL ROAD BRIDGE OVER I-57 SUMMARY OF QUANTITIES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE * #SCALE#	DRAWN - BES	REVISED -		SCALE: N.T.S.	SHEET NO. 1 OF 5 SHEETS	STA. TO STA.	57	99-IHB-R	WILL	63	4	
	PLOT DATE * 4/4/2012	CHECKED - JPM	REVISED -		CONTRACT NO. 60T40			ILLINOIS FED. AID PROJECT					
		DATE - 3/30/2012	REVISED -										