

ROUTE: I-55 East Frontage Rd. (North of IL 113 to Stripmine Rd.)							
CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
0.1mi. N of IL 113 NB		NB	1	12	10	120	13
		SB	1	12	10	120	13
		NB	1	3	50	150	17
		SB	1	12	40	480	53
		SB	1	12	50	600	67
		SB	1	6	30	180	20
		NB	1	3	10	30	3
		NB	1	6	20	120	13
		SB	1	8	30	240	27
		NB	1	12	30	360	40
		NR	1	6	15	90	10
		NB	1	6	50	300	33
		SB	1	12	50	600	67
		SB	1	8	100	800	89
		NB	1	3	100	300	33
	Res. @ 32105 E. Frt. Rd. NB		NB	1	6	20	120
		NB	1	3	50	150	17
		SB	1	12	30	360	40
		SB	1	3	10	30	3
		NB	1	12	30	360	40
		SB	1	10	20	200	22
	Private Club Ent. NB	SB	1	3	20	60	7
		SB	1	4	20	80	9
		NB	1	3	10	30	3
		NB	1	6	10	60	7
		NB	1	12	20	240	27
		SB	1	10	50	500	56
		NB	1	3	10	30	3
		SB	1	10	20	200	22
		NB	1	4	12	48	5
		NB	1	10	30	300	33
		SB	1	6	50	300	33
		SB	1	4	40	160	18
		SB	1	6	12	72	8
	Comm. Ent. @ 24917	SB	1	4	25	100	11
		SB	1	12	30	360	40
		SB	1	8	20	160	18
	End Project	SB	1	6	50	300	33
		TOTALS:				1184	968
						FT	SY

ROUTE: I-80 Frontage Rd. (At Larkin Ave. and I-80 (Southwest Corner))							
CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
at Larkin Ave		EB	1	12	700	8400	933
				10	150	1500	167
				4	50	200	22
				4	15	60	7
				6	75	450	50
				4	25	100	11
				6	75	450	50
				4	25	100	11
				6	75	450	50
		I-80			4	30	120
I-80		WB	1	12	40	480	53
				6	40	240	27
				6	50	300	33
				6	30	180	20
				4	40	160	18
				4	30	120	13
	at Larkin Ave			4	25	100	11
		TOTALS:				1475	1490
						FT	SY

ROUTE: Frontage Rd. (US 45 and US 52) - SW Corner								
CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR	
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA	
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)	
US 45		NB	1	12	8	96	11	
		NB	1	12	6	72	8	
		NB	1	12	6	72	8	
		NB	1	12	6	72	8	
		NB	1	12	6	72	8	
		NB	1	12	6	72	8	
		NB	1	12	6	72	8	
		NB	1	12	6	72	8	
		NB	1	12	20	240	27	
		US 52	NB	1	12	8	96	11
US 52		SB	1	12	15	180	20	
		SB	1	12	6	72	8	
		SB	1	12	50	600	67	
		SB	1	4	100	400	44	
		SB	1	12	8	96	11	
		SB	1	4	100	400	44	
		US 45	SB	1	12	8	96	11
		TOTALS:				365	309	
						FT	SY	

FILE NAME =	USER NAME = chrzesclr	DESIGNED -	REVISED -
et:\pw\work\p\dot\chrzesclr\d0303672\013	9912-Design.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/10/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PATCHING SCHEDULE
I-55 E. FRONTAGE RD., I-80 FRONTAGE RD. & FRONTAGE RD.**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2012-015 RS	WILL	27	18
			CONTRACT NO. 60T61	
ILLINOIS FED. AID PROJECT				