

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE COOK CO. 0005	100% STATE WILL CO. 0005				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	13	2				
40600300	AGGREGATE (PRIME COAT)	TON	72	63	9				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	54	47	7				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1061	937	124				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3960	3497	463				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	35344	31217	4127				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	0.9	0.1				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4069	3462	607				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1711	1509	202				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	550	518	32				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	43447	37082	6365				

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE COOK CO. 0005	100% STATE WILL CO. 0005				
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	2265		2265				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1310	1000	310				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	250	250					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	250	250					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	532	508	24				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	790	591	199				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	790	591	199				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1700	1650	50				
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	1132	1080	52				
	* SPECIALTY ITEM								

FILE NAME =	USER NAME = percip	DESIGNED -	REVISED -
c:\p\work\paw\percip\0303732\040212-Design.dwg		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2012-018 RS	COOK & WILL	29	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60T64	