ROUTE	: Justamere Rd. (1	43rd St. to 147	'th St.)				
CROS	S STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPA
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	ARE
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ Y
143rd St		SB	1	12	150	1800	200
		SB	1	12	50	600	67
		SB	1	12	80	960	107
		SB	1	12	8	96	11
		SB	1	6	20	120	13
		SB	1	6	50	300	33
	147th St	SB	1	6	50	300	33
147th St		NB	1	6	200	1200	133
		NB	1	6	75	450	50
		NB	1	12	30	360	40
		NB	1	6	800	4800	533
	143rd St	NB	1	12	150	1800	200
		TOTALS:			1663		142 <sup>,</sup>
					FT		SY

DOUTE		1.00					
ROUTE	: Wolf Rd.(159th St. to	5 1-80)					
CROS	S STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD)
159th Street		SB	1	3	400	1200	133
		SB	1	3	200	600	67
		SB	1	3	500	1500	167
		SB	1	6	50	300	33
	167th Street	SB	1	3	600	1800	200
167th Street		SB	1	3	100	300	33
		SB	1	12	10	120	13
	Brook Hill Drive	SB	1	6	50	300	33
US 6		SB	1	12	300	3600	400
		SB	1	12	50	600	67
		SB	1	6	200	1200	133
		SB	1	6	200	1200	133
		SB	1	12	400	4800	533
		SB	1	6	200	1200	133
	179th Street	SB	1	12	20	240	27
179th Street		SB	1	12	100	1200	133
		SB	1	3	100	300	33
		SB	1	6	200	1200	133
		SB	1	3	800	2400	267
		SB	1	6	200	1200	133
		SB	1	12	6	72	8
	I-80	SB	1	12	6	72	8

ROUTE	Wolf Rd.(159th St. 1	o I-80) (Continu	led)				
	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD
I-80		NB	1	6	12	72	8
		NB	1	6	12	72	8
		NB	1	6	12	72	8
		NB	1	6	12	72	8
		NB	1	6	12	72	8
		NB	1	6	200	1200	133
		NB	1	3	200	600	67
		NB	1	6	12	72	8
		NB	1	3	200	600	67
		NB	1	3	300	900	100
	179th Street	NB	1	3	150	450	50
179th Street		NB	1	6	12	72	8
		NB	1	12	200	2400	267
		NB	1	12	10	120	13
		NB	1	12	150	1800	200
		NB	1	12	500	6000	667
		NB	1	12	200	2400	267
		NB	1	12	200	2400	267
		NB	1	12	100	1200	133
		NB	1	12	50	600	67
	US 6	NB	1	12	200	2400	267
Brook Hill Drive		NB	1	6	12	72	8
		NB	1	6	50	300	33
		NB	1	6	50	300	33
		NB	1	6	300	1800	200
		NB	1	6	600	3600	400
		NB	1	6	100	600	67
		NB	1	6	200	1200	133
		NB	1	6	12	72	8
		NB	1	6	200	1200	133
		NB	1	6	100	600	67
	167th Street	NB	1	6	100	600	67
167th Street		NB	1	15	20	300	33
		NB	1	12	100	1200	133
		NB	1	6	200	1200	133
		NB	1	6	50	300	33
		NB	1	6	100	600	67
		NB	1	12	20	240	27
		NB	1	6	100	600	67
		NB	1	6	100	600	67
		NB	1	12	30	360	40
		NB	1	6	100	600	67
		NB	1	6	150	900	100
		NB	1	12	12	144	16
	159th Street	NB	1	6	150	900	100
		TOTALS:			10292		7474
					FT		SY

FILE NAME =	USER NAME = pencepl	DESIGNED -	REVISED -			PATCHING SCHEDULE					F.A	SECTION	COUNTY	TOTAL SHEET
c:\pw_work\pwidot\pencepl\d0303732\D140	12-Design.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS		JUSTAMERE RD. AND WOLF RD.				VAR.	2012-018 RS	COOK & WIL	L 29 7	
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	JUSTAWIEKE KD. AND WULF KD.				_		CONTRAC	T NO. 60T64		
	PLOT DATE = 4/5/2012	DATE -	REVISED -		SCALE:	SCALE: SHEET OF SHEETS STA. TO STA.				TO STA.		ILLINOIS FED.	AID PROJECT	