

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				95TH ST AT CICERO AVE	95TH ST AT KOSTNER AVE	
				90% FED 10% STATE	90% FED 10% STATE	
				TRAFFIC SIGNALS 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	152		152	
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	9		9	
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	48		48	
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	376		376	
81400100	HANDHOLE	EACH	2		2	
81400200	HEAVY-DUTY HANDHOLE	EACH	1		1	
81400300	DOUBLE HANDHOLE	EACH	2		2	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1		
86400100	TRANSCEIVER - FIBER OPTIC	EACH	2	1	1	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1152		1152	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	3008	927	2081	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2406	934	1472	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1779		1779	
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1746		1746	

* SPECIALTY ITEMS * * 100% VILLAGE OF OAK LAWN

FILE NAME = MICROST\352098\ 03-SUMMARY.DGN	USER NAME = JGC	DESIGNED - BPT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (SHEET 2 OF 6)				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
		DRAWN - JGC	REVISED -		SCALE: N.T.S.	SHEET NO.	OF	SHEETS	STA.	TO STA.	029	2012-028 TS	COOK	26	4
		CHECKED - BPT	REVISED -												
		DATE - 10-21-11	REVISED -												
											CONTRACT NO. 60T81				
											FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				