

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				95TH ST AT CICERO AVE	95TH ST AT KOSTNER AVE	
				90% FED 10% STATE	90% FED 10% STATE	
				TRAFFIC SIGNALS 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	
89502380	REMOVE EXISTING HANDHOLE	EACH	3		3	
89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	1		1	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5		5	
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1	
X8570231	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1	1		
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	2	1	1	
** X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	239		239	
X8803040	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED, RETROFIT	EACH	1	1		
X8803084	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED, RETROFIT	EACH	11	11		
X8803088	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED, RETROFIT	EACH	1	1		
X8803090	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED, RETROFIT	EACH	3	3		
X8810617	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED, RETROFIT	EACH	8	8		
X8950100	RELOCATE EXISTING MASTER CONTROLLER	EACH	2	2		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	25.7	25.7	

* SPECIALTY ITEMS

** 100% VILLAGE OF OAK LAWN

FILE NAME = MICROST\352896\ 03-SUMMARY.DGN	USER NAME = JGC	DESIGNED - BPT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (SHEET 5 OF 6)				F.A.P. RTE. 029	SECTION 2012-028 TS	COUNTY COOK	TOTAL SHEETS 26	SHEET NO. 7
PLOT SCALE = NONE	CHECKED - BPT	REVISED -			SCALE: N.T.S.	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		
PLOT DATE = 10-21-11	DATE - 10-21-11	REVISED -			CONTRACT NO. 60T81								