

DATE	BY	SURVEYED	PLOTTED	TEMPLATE	AREAS	CHECKED
		FINAL SURVEY	NOTE BOOK	NO.		

DATE	BY	SURVEYED	PLOTTED	TEMPLATE	AREAS	CHECKED
		ORIGINAL SURVEY	NOTE BOOK	NO.		

CODED PAY ITEM NO.	PAY ITEM	UNIT	TOTAL QUANTITY	0003	0021
				ROADWAY	SIGNALS
55101600	STORM SEWER REMOVAL, 36"	FOOT	480	480	
55201300	STORM SEWERS JACKED IN PLACE, 36"	FOOT	112	112	
* 56107200	REMOVE AND RELOCATE WATER MAIN 8"	FOOT	20	20	
^ 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	50	50	
^ 56300300	ADJUSTING WATER SERVICE LINES	FOOT	50	50	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	52	52	
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2	
60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	10	10	
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	36	36	
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	4	4	
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1	
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	6	6	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9	9	
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	26	26	
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2	
60224039	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1	
60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	4	4	
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	23	23	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	4	4	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2	
60255500	MANHOLES TO BE ADJUSTED	EACH	6	6	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2	
60258100	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1	
60260100	INLETS TO BE ADJUSTED	EACH	4	4	
60262700	INLETS TO BE RECONSTRUCTED	EACH	2	2	
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1	
60500040	REMOVING MANHOLES	EACH	16	16	
60500050	REMOVING CATCH BASINS	EACH	17	17	
60500060	REMOVING INLETS	EACH	14	14	
60600605	CONCRETE CURB, TYPE B	FOOT	279	279	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	13,923	13,923	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	147	147	
60624600	CORRUGATED MEDIAN	SQ FT	1,290	1,290	
* 61140200	STORM SEWERS (SPECIAL), 12"	FOOT	56	56	
^ 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	226	226	
* ^ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	
63200310	GUARDRAIL REMOVAL	FOOT	447	447	
^ 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	79	79	
^ 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	

^ DENOTES SPECIALTY ITEM
 ^^ DENOTES CONSTRUCTION TYPE CODE 0042
 * DENOTES SPECIAL PROVISION

CODED PAY ITEM NO.	PAY ITEM	UNIT	TOTAL QUANTITY	0003	0021
				ROADWAY	SIGNALS
^ 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	15	15	
67100100	MOBILIZATION	L SUM	1	1	
67201000	SEALING ABANDONED WATER WELLS	EACH	1	1	
67201100	SEALING ABANDONED MONITORING WELLS	EACH	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,831	2,831	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	1,475	1,475	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	70,560	70,560	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6,919	6,919	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	643	643	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	842	842	
^ 70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	110	110	
^ 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	13,963	13,963	
^ 70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	415	415	
^ 70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	524	524	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	37,222	37,222	
^ 72000100	SIGN PANEL - TYPE 1	SQ FT	40	25	15
^ 72000200	SIGN PANEL - TYPE 2	SQ FT	43	20	23
^ 72000300	SIGN PANEL - TYPE 3	SQ FT	60	60	
^ 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	54	54	
^ 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	407	407	
^ 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	564	564	
^ 73400100	CONCRETE FOUNDATIONS	CU YD	1.4	1.4	
^ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,552	2,552	
^ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	28,310	28,310	
^ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	10,090	10,090	
^ 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4,912	4,912	
^ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	5,282	5,282	
^ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,114	1,114	
^ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	194	194	
* ^ 78200420	GUARDRAIL MARKERS, TYPE B	EACH	3	3	
* ^ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1	
^ 78300100	PAVEMENT MARKING REMOVAL	SQ FT	9,297	9,297	
^ 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	150	150	
* ^ 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2		2
^ 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	4,330		4,330
^ 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	181		181
^ 81028230	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3 1/2" DIA.	FOOT	288		288
^ 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1,822		1,822

^ DENOTES SPECIALTY ITEM
 ^^ DENOTES CONSTRUCTION TYPE CODE 0042
 * DENOTES SPECIAL PROVISION

CIVILTECH
 450 E Devon Ave, Suite 300
 Itasca, Illinois 60143
 Tel: 630.773.3900 Fax: 630.773.3975
 www.civiltechinc.com

DESIGNED - JRR	REVISED -
DRAWN - JRR	REVISED -
CHECKED - RTM	REVISED -
DATE - 10/24/2011	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SHEET NO. 2 OF 4 SHEETS

F.A.U. RTE. 364	SECTION 02-00051-08-WR	COUNTY LAKE	TOTAL SHEETS 188	SHEET NO. 5
CONTRACT NO. 63649				

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT