

DATE _____ BY _____
 SURVEYED _____ PLOTTED _____
 FINAL SURVEY _____ NOTE BOOK _____
 NO. _____ AREAS CHECKED _____

DATE _____ BY _____
 SURVEYED _____ PLOTTED _____
 ORIGINAL SURVEY _____ NOTE BOOK _____
 NO. _____ AREAS CHECKED _____

6 SCHEDULE OF HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 (40603085)				
FROM	TO	AREA @ 8-1/2" (SQ YD)	TOTAL VOLUME (SQ YD-IN)	WEIGHT (115 LB/SQ YD-IN) (TON)
19+71	23+00	2,194	18,646	1,073
23+00	28+00	3,330	28,308	1,628
28+00	33+00	4,562	38,775	2,230
33+00	38+00	2,740	23,292	1,340
38+00	43+80	4,505	38,296	2,203
43+80	1+30	2,192	18,632	1,072
1+30	5+00	3,311	28,144	1,619
5+00	9+00	4,561	38,770	2,230
9+00	14+00	3,718	31,599	1,817
14+00	19+00	2,509	21,329	1,227
19+00	24+00	182	1,548	89
101+80	105+00	227	1,926	111
107+00	110+20	1,728	14,689	845
PROJECT TOTAL				17,484

7 SCHEDULE OF TOPSOIL FURNISH AND PLACE					
		(21101615) 4"		(21101685) 24"	
FROM	TO	AREA (SQ FT)	AREA (SQ YD)	AREA (SQ FT)	AREA (SQ YD)
19+71	32+00	28,263	3,141	0	0
32+00	11+00	217,745	24,194	12,102	1,345
11+00	24+00	47,571	5,286	5,678	631
101+80	110+20	29,319	3,258	0	0
PROJECT TOTAL			35,879		1,976

8 SCHEDULE OF HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (40603340)					
FROM	TO	AREA @ 2" (SQ YD)	AREA @ 1-1/2" (SQ YD)	TOTAL VOLUME (SQ YD-IN)	WEIGHT (112 LB/SQ YD-IN) (TON)
19+71	23+00	2,194	0	4,387	246
23+00	28+00	3,330	0	6,660	373
28+00	33+00	4,562	0	9,124	511
33+00	38+00	2,740	0	5,480	307
38+00	43+80	4,505	0	9,011	505
43+80	1+30	2,192	0	4,384	246
1+30	5+00	3,311	0	6,622	371
5+00	9+00	4,561	0	9,122	511
9+00	14+00	3,718	0	7,435	417
14+00	19+00	2,869	0	5,738	322
19+00	24+00	2,558	0	5,116	287
101+80	105+00	227	1645	2,921	164
107+00	110+20	1,728	0	3,456	194
PROJECT TOTAL					4,454

9 SCHEDULE OF HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (40603335)						
FROM	TO	AREA @ 1-1/2" (SQ YD)	AREA @ 2-1/2" (SQ YD)	AREA @ 3" (SQ YD)	TOTAL VOLUME (SQ YD-IN)	WEIGHT (112 LB/SQ YD-IN) (TON)
19+71	23+00	314	0	0	471	27
23+00	28+00	444	0	0	666	38
28+00	33+00	288	0	0	431	25
33+00	38+00	437	22	0	710	40
38+00	43+80	478	68	0	888	62
43+80	1+30	32	0	0	48	3
1+30	5+00	278	0	0	418	24
5+00	9+00	186	0	236	985	56
9+00	14+00	204	88	543	2,156	121
14+00	19+00	274	41	355	1,577	89
19+00	24+00	387	106	0	846	48
101+80	105+00	5	0	0	8	1
107+00	110+20	0	49	0	122	7
PROJECT TOTAL						541

10 SCHEDULE OF TEMPORARY PAVEMENT (Z0062456)		
FROM	TO	AREA (SQ YD)
19+00	34+00	80
34+00	3+00	773
3+00	15+00	348
15+00	24+50	21
101+80	110+20	446
PROJECT TOTAL		1,668

11 SCHEDULE OF SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING (Z0023202)		
FROM	TO	AMOUNT (EACH)
19+71	32+00	18
32+00	11+00	52
11+00	24+50	19
101+80	110+20	2
PROJECT TOTAL		91

12 SCHEDULE OF RAISED REFLECTIVE PAVEMENT MARKERS (78100100)			
FROM	TO	SIDE	AMOUNT (EACH)
15+00	34+00	RT	44
15+00	34+00	LT	38
34+00	3+00	RT	31
34+00	3+00	LT	32
3+00	15+00	RT	17
3+00	15+00	LT	28
15+00	23+66	RT	0
15+00	23+66	LT	4
101+80	110+20	RT	0
101+80	110+20	LT	0
PROJECT TOTAL			194

13 SCHEDULE OF COMBINATION CURB AND GUTTER, TYPE B-6.24 (60605000)		
FROM	TO	LENGTH (FOOT)
19+71	23+00	659
23+00	28+00	1,000
28+00	33+00	1,130
33+00	38+00	2,001
38+00	43+80	1,575
43+80	1+30	700
1+30	5+00	1,257
5+00	9+00	903
9+00	14+00	1,435
14+00	19+00	1,624
19+00	24+50	972
101+80	105+00	26
107+00	110+20	641
PROJECT TOTAL		13,923

14 SCHEDULE OF STORM SEWER REMOVAL AND TRENCH BACKFILL										
STATION		55100100	55100300	55100400	55100500	55100700	55100900	55101200	55101600	20800150
FROM	TO	SS REM 4" (FOOT)	SS REM 8" (FOOT)	SS REM 10" (FOOT)	SS REM 12" (FOOT)	SS REM 15" (FOOT)	SS REM 18" (FOOT)	SS REM 24" (FOOT)	SS REM 36" (FOOT)	TRNCH BKFILL (CU YD)
19+71	23+00									
23+00	28+00	126			267	104	171	60		264
28+00	33+00				164	325			27	363
33+00	38+00					49			381	449
38+00	43+80	268				146				114
43+80	1+30	30		135	55					69
1+30	5+00		2		41	282		38	72	189
5+00	9+00				118			111		241
9+00	14+00				34	43				12
14+00	19+00	251			67	31		102		239
19+00	24+50				209					54
101+80	105+00									
107+00	110+20									
PROJECT TOTAL		675	2	135	955	980	171	311	480	1,994*

*FOR ADDITIONAL TRENCH BACKFILL QUANTITY SEE SCHEDULE *21