

15													
SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION													
QUENTIN AVENUE, LONG GROVE ROAD													
STATION	DISTANCE	EARTH EXCAVATION (CUT)	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SUBGRADE (PGES)	FURNISHED EXCAVATION (FILL)	EARTH EXCAVATION	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SUBGRADE (PGES)	FURNISHED EXCAVATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL ⁽¹⁾	POROUS GRANULAR EMBANKMENT, SUBGRADE (PGES)	FURNISHED EXCAVATION ⁽²⁾
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)
19+50	50	0	0	0	0	7	5	0	15	325	250	0	725
20+00	50	13	10	0	29	15	5	0	38	725	250	0	1,900
20+50	50	16		0	47	15	8	0	39	725	400	0	1,925
21+00	50	13	16	0	30	16	19	0	31	775	950	0	1,525
21+50	50	18	22	0	31	20	23	0	29	975	1,150	0	1,425
22+00	50	21	24	0	26	21	27	0	26	1,025	1,350	0	1,300
22+50	50	20	30	0	26	31	34	0	30	1,525	1,700	0	1,475
23+00	50	41	38	0	33	48	37	0	35	2,400	1,850	0	1,725
23+50	50	55	36	0	36	71	39	0	32	3,525	1,950	0	1,575
24+00	50	86	42	0	27	90	44	0	27	4,475	2,200	0	1,325
24+50	50	93	46	0	26	77	45	0	27	3,850	2,225	0	1,350
25+00	50	61	43	0	28	48	45	0	32	2,375	2,225	0	1,600
25+50	50	34	46	0	36	33	44	0	36	1,625	2,175	0	1,800
26+00	50	31	41	0	36	28	41	0	39	1,375	2,050	0	1,925
26+50	50	24	41	0	41	29	75	35	35	1,450	3,725	1,725	1,725
27+00	50	34	108	69	28	38	108	69	26	1,900	5,375	3,450	1,275
27+50	50	42	107	69	23	43	104	69	19	2,150	5,200	3,450	950
28+00	50	44	101	69	15	49	108	73	17	2,450	5,375	3,625	825
28+50	50	54	114	76	18	126	153	113	11	6,275	7,625	5,650	550
29+00	50	197	191	150	4	184	183	155	6	9,175	9,150	7,750	275
29+50	50	170	175	160	7	174	120	80	13	8,700	6,000	4,000	625
30+00	50	178	65	0	18	164	59	0	25	8,175	2,925	0	1,250
30+50	50	149	52	0	32	129	52	0	35	6,425	2,600	0	1,750
31+00	50	108	52	0	38	68	50	0	44	3,400	2,500	0	2,200
31+50	50	28	48	0	50	21	54	0	95	1,050	2,700	0	4,725
32+00	50	14	60	0	139	13	491	47	461	625	24,525	2,325	23,050
32+50	50	11	921	93	783	754	878	93	699	37,700	43,900	4,625	34,925
33+00	50	1,497	835	92	614	1,231	794	92	627	61,550	39,700	4,600	31,350
33+50	50	965	753	92	640	810	675	91	591	40,500	33,750	4,525	29,550
34+00	50	655	597	89	542	536	598	90	509	26,775	29,900	4,500	25,450
34+50	50	416	599	91	476	246	595	93	446	12,275	29,725	4,625	22,300
35+00	50	75	590	94	416	46	474	96	614	2,275	23,675	4,800	30,700
35+50	50	16	357	98	812	13	353	100	583	650	17,650	5,000	29,150
36+00	50	10	349	102	354	13	353	104	363	650	17,625	5,175	18,125
36+50	50	16	356	105	371	15	360	106	399	725	17,975	5,300	19,925

DATE _____ BY _____
 SURVEYED _____
 PLOTTED _____
 NOTE BOOK _____
 AREAS CHECKED _____

DATE _____ BY _____
 ORIGINAL SURVEY _____
 PLOTTED _____
 NOTE BOOK _____
 AREAS CHECKED _____