SUMMARY OF QUANTITIES

	PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY 80% FEDERAL 20% LOCAL 0004	SIGNALS 80% FEDERAL 20% LOCAL 0021	LIGHTING 80% FEDERAL 20% LOCAL 0021
*	87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	42		42	
*	87900200	DRILL EXISTING HANDHOLE	EACH	10		10	
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	2		2	
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	8		8	
*	88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4		4	
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4		4	
*	88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	14		14	
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	2		2	
*	88600100	DETECTOR LOOP, TYPE 1	FOOT	1,049		1,049	
*	88700200	LIGHT DETECTOR	EACH	2		2	
*	88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1	
*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	4		4	
*	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1	
*	89502200	MODIFY EXISTING CONTROLLER	EACH	1		1	
*	89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1		1	
*	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	7,241		6,941	300
*	89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	5,885		5,885	
*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1	
*	89502380	REMOVE EXISTING HANDHOLE	EACH	6		5	1
*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	4		4	
	X0322936	REMOVE EXISTING FLARED END SECTION	EACH	2	2		
*	X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	336		336	
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1		
	X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	3,310	3,310		
*	X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1			1
*	X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1		1	
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
	Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	2	2		
	Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	8	8		
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	105	105		
*	Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	7			7
*	Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	3			3
*	Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1		1	
	Z0042002	POROUS GRANULAR EMBANKEMENT, SUBGRADE	CU YD	1,474	1,474		
	Z0066600	STABILIZED DRIVEWAYS 8"	SQ YD	75	75		
	Z0070200	SURVEY MONUMENTS	EACH	1	1		
*	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1	
X	Z0076600	TRAINEES	HOUR	500	500		

* SPECIALTY ITEM

X CONSTRUCTION TYPE CODE 0042

COMPANY NAME:
PROJECT CONTACT:
CLIENT:
DATE PLOTTED: 4/11/2012 3:43:45 PM
FILE NAME: 0177-sum.dgn
PLOT DRIVER: pdfsplit
PEN TABLE: standard-trans.tbl

COOK
10-00084-00-CH
0177-sum.dgn

HRGreen.com
Illinois Professional Design Firm
184-001322

USER NAME = jmelhus	DESIGNED - JRM	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = N.T.S.	CHECKED - TEH	REVISED -
PLOT DATE = 4/11/2012	DATE - 4/11/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL 59 & SHOE FACTORY RD

SCALE: N.T.S. | SHEET NO. 3 OF 3 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	10-00084-00-CH	COOK	63	5
•		CONTRACT NO. 63711		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT