

ILLINOIS ROUTE 59			
STATION	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL	FURNISHED EXCAVATION	POROUS GRANULAR EMBANKMENT, SUBGRADE
507+66.17	0.0	0.0	0.0
508+00.00	18.0	0.0	5.3
508+50.00	54.3	0.3	19.7
508+90.14	63.7	0.8	22.9
509+00.00	18.6	0.5	6.7
509+50.00	107.2	6.0	39.0
510+00.00	126.7	5.2	44.0
510+14.46	39.2	0.3	13.0
510+50.00	94.6	0.3	31.3
511+00.00	125.4	0.6	42.6
511+40.00	136.3	0.3	48.5
512+30.00	0.0	0.0	0.0
512+50.00	52.9	0.2	11.1
513+00.00	137.6	2.8	48.8
513+50.00	121.7	3.9	43.2
513+93.11	111.0	1.9	38.5
514+00.00	18.0	0.2	6.1
514+50.00	140.3	5.4	47.3
515+00.00	186.0	9.4	63.3
515+15.48	69.1	2.9	23.8
515+50.00	155.4	5.9	53.1
516+00.00	217.2	6.8	76.7
516+40.50	158.9	2.3	57.1
516+50.00	33.4	0.1	11.9
517+00.00	145.5	0.3	53.1
517+50.00	100.6	0.1	37.0
TOTALS	2,431.5	56.4	844.1
	(CU YD)	(CU YD)	(CU YD)

SHOE FACTORY ROAD			
STATION	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL	FURNISHED EXCAVATION	POROUS GRANULAR EMBANKMENT, SUBGRADE
107+89.36	0.0	0.0	0.0
108+00.00	1.4	0.1	0.0
108+50.00	16.9	0.3	4.4
109+00.00	38.2	2.8	13.4
109+50.00	60.0	6.9	22.6
110+00.00	78.5	7.9	30.3
110+50.00	87.5	5.2	33.3
111+00.00	87.7	4.5	33.3
111+50.00	85.6	6.2	33.3
111+90.00	175.5	3.8	66.8
112+00.00	83.4	1.1	32.1
113+10.00	0.0	0.0	0.0
113+40.00	125.8	0.8	45.4
113+50.00	28.2	0.1	8.9
113+56.83	16.7	1.1	5.8
114+00.00	92.4	13.1	36.2
114+50.00	109.0	14.2	41.9
115+00.00	111.1	11.7	41.9
115+50.00	117.8	8.1	42.2
116+00.00	120.6	7.8	42.4
116+50.00	107.4	9.3	38.4
117+00.00	93.9	5.4	29.5
117+32.09	45.2	1.4	13.8
117+50.00	18.3	0.6	6.1
118+00.00	29.2	0.1	8.0
TOTALS	1,730.4	112.3	630.2
	(CU YD)	(CU YD)	(CU YD)

NOTE:
ESTIMATED VALUE OF POROUS GRANULAR EMBANKMENT, SUBGRADE. ACTUAL QUANTITY TO BE DETERMINED IN THE FIELD.

HR GREEN, INC.
COMPANY NAME
PROJECT CONTACT: J. MELHUISH
CLIENT: VILLAGE OF HOFFMAN ESTATES
DATE PLOTTED: 4/5/2012 5:38:45 PM
FILE NAME: 0177-sch.dgn
PLOT DATE: 4/5/2012
PLOT SCALE: N.T.S.

0177-sch.dgn
5:38:45 PM
4/5/2012



USER NAME = Spennel	DESIGNED - JRM	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = N.T.S.	CHECKED - TEH	REVISED -
PLOT DATE = 4/5/2012	DATE - 4/5/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
IL 59 & SHOE FACTORY RD

SCALE: N.T.S. SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	10-00084-00-CH	COOK	63	6
CONTRACT NO.			63711	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		