SCHEDULE OF QUANTITIES

60618300 CONCRETE MEDIAN SURFACE, 4 INCH

SQ FT	LOCATION		OFFSET	REMARKS
	IL ROUTE 2			
1,764	217+06	218+71.68	MEDIAN	
19,611	232+28.07	241+36.76	MEDIAN	
7,851	327+18.79	331+85.12	MEDIAN	
	ONYX PARKWAY			
136	228+82	229+02	ISLAND	
	SPRINGFIELD/HARRISON			
928	28+04.36	29+03.21	MEDIAN	
763	38+79.92	39+70.13	MEDIAN	
	PRAIRIE ROAD			
131	ISLAND			
	IL ROUTE 2/HARRISON			
954	N/W ISLAND			
367	S/W ISLAND			
288	N/E ISLAND			
410	S/E ISLAND			
33,203	TOTAL			

60623745 CONCRETE MEDIAN TRANSITION

SQ FT	LOCATION		OFFSET	REMARKS
	IL ROUTE 2			
118	232+21.95	232+32	MEDIAN	
118	TOTAL			

60624600 CORRUGATED MEDIAN

SQ FT	LOCATION		OFFSET	REMARKS
794	311+30.56	312+29.56	LT TURN LN	
794	TOTAL			

63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS

FOOT	LOCATION		OFFSET	REMARKS
	HARRISON AVENUE			
375.0	36+95.9	40+70.1	LT	
137.5	39+39.9	40+77.4	RT	
512.5	TOTAL			

63100045 TRAFFIC BARRIER TERMINAL, TYPE 2

EACH	LOCATION		OFFSET	REMARKS
	HARRISON AVENUE			
1	36+83.4	36+95.9	LT	
1	TOTAL			

63100070 TRAFFIC BARRIER TERMINAL, TYPE 5

EACH	LOCATION		OFFSET	REMARKS
	HARRISON AVENUE			
1	40+70.1	40+84.7	LT	
1	TOTAL			

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6

EACH	LOCATION		OFFSET	REMARKS
	HARRISON AVENUE			
1	40+77.4	41+21.4	RT	
1	TOTAL			

63100169 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED

EACH	LOCATION		OFFSET	REMARKS
	HARRISON AVENUE			
1	38+90.1	39+39.9	RT	
1	TOTAL			

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION		OFFSET	REMARKS
	SPRINGFIELD / HARRISON			
34	32+16	32+49	LT	
463	36+22	40+85	LT	
238	38+84	41+21	RT	
735	TOTAL			

64200116 SHOULDER RUMBLE STRIPS, 16 INCH

FOOT	LOCATION		OFFSET	REMARKS
722	253+78	261+00	LT	
357	253+78	257+35	RT	
1,079	TOTAL			

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	OFFSET	REMARKS
4	AS DETERMINED BY IDOT CHIEF OF SURVEYS		
4	TOTAL		

72000100 SIGN PANEL - TYPE 1

SQ FT	LOCATION	REMARKS
	AQUAMARINE DRIVE	
9.0	N/E CORNER	R1-1, 36" x 36", "STOP"
2.0	N/E CORNER	W4-4P, 24" x 12", "CROSS TRAFFIC DOES NOT STOP"
	PELLEY ROAD	
9.0	N/E CORNER	R1-1, 36" x 36", "STOP"
2.0	N/E CORNER	W4-4P, 24" x 12", "CROSS TRAFFIC DOES NOT STOP"
9.0	S/W CORNER	R1-1, 36" x 36", "STOP"
2.0	S/W CORNER	W4-4P, 24" x 12", "CROSS TRAFFIC DOES NOT STOP"
	ONYX PARKWAY	
9.0	ISLAND	R1-1, 36" x 36", "STOP"
9.0	N/E CORNER	R1-1, 36" x 36", "STOP"
	FAITH CENTER ENTRANCE	
9.0	S/W CORNER	R1-1, 36" x 36", "STOP"
2.0	S/W CORNER	W4-4P, 24" x 12", "CROSS TRAFFIC DOES NOT STOP"
	SW RAMP	
9.0	S/W CORNER	R1-1, 36" x 36", "STOP"
4.5	S/W CORNER	W4-4P, 36" x 18", YEL, "TRAFFIC FROM LEFT DOES NOT STOP
9.0	N/W CORNER	R1-1, 36" x 36", "STOP"
4.5	N/W CORNER	W4-4P, 36" x 18", YEL, "TRAFFIC FROM LEFT DOES NOT STOP
	SEMINOLE AVENUE	
9.0	N/E CORNER	R1-1, 36" x 36", "STOP"
	PRAIRIE ROAD	
9.0	ISLAND	R1-1, 36" x 36", "STOP"
9.0	S/W CORNER	R1-1, 36" x 36", "STOP"
	EXPRESS LANE	
9.0	S/E CORNER	R1-1, 36" x 36", "STOP"
125.0	TOTAL	

73000100 WOOD SIGN SUPPORT

FOOT	LOCATION	REMARKS
	AQUAMARINE DRIVE	
14	N/E CORNER	4" x 6"
	PELLEY ROAD	
14	N/E CORNER	4" x 6"
14	S/W CORNER	4" x 6"
	ONYX PARKWAY	
14	ISLAND	4" x 6"
14	N/E CORNER	4" x 6"
	FAITH CENTER ENTRANCE	
14	S/W CORNER	4" x 6"
	SW RAMP	
14	S/W CORNER	4" x 6"
14	N/W CORNER	4" x 6"
	SEMINOLE AVENUE	
14	N/E CORNER	4" x 6"
	PRAIRIE ROAD	
14	ISLAND	4" x 6"
14	S/W CORNER	4" x 6"
	EXPRESS LANE	
14	S/E CORNER	4" x 6"
168	TOTAL	

73600200 REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER

EACH	LOCATION	OFFSET	REMARKS
1	237+81	62.5' RT	
1	TOTAL		

73700300 REMOVE CONCRETE FOUNDATION - OVERHEAD

EACH	LOCATION	OFFSET	REMARKS
1	237+81	62.5' RT	
1	TOTAL		

78009000 MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS

SQ FT	LOCATION		REMARKS
	WHITE		
	IL ROUTE 2		
15.6	219+70	SB LT TL	LT ARROW
15.6	220+30	SB LT TL	LT ARROW
15.6	222+07	NB LT TL	LT ARROW
15.6	222+47	NB LT TL	LT ARROW
15.6	222+87	NB LT TL	LT ARROW
15.6	224+58	SB LT TL	LT ARROW
15.6	225+23	SB LT TL	LT ARROW
15.6	225+88	SB LT TL	LT ARROW
15.6	226+53	SB LT TL	LT ARROW
15.6	227+85	NB LT TL	LT ARROW
15.6	228+60	NB LT TL	LT ARROW
15.6	229+35	NB LT TL	LT ARROW
15.6	230+10	NB LT TL	LT ARROW
15.6	230+85	NB LT TL	LT ARROW
15.6	232+75	SB RT TL	RT ARROW
15.6	233+33	SB RT TL	RT ARROW
15.6	233+92	SB RT TL	RT ARROW
15.6	234+50	SB RT TL	RT ARROW
15.6	267+28	NB RT TL	RT ARROW
15.6	267+28	NB LT TL	LT ARROW
15.6	268+03	NB RT TL	RT ARROW
15.6	268+03	NB LT TL	LT ARROW
15.6	268+79	NB RT TL	RT ARROW
15.6	268+79	NB LT TL	LT ARROW