

SCHEDULE OF QUANTITIES

CONTINUED

78100100 RAISED REFLECTIVE PAVEMENT MARKER				
EACH	LOCATION	OFFSET		REMARKS
22	260+97	264+97	SB GORE	ONE-WAY
11	261+38	269+80	NB THRU RT	ONE-WAY
14	267+07	269+80	NB LT TL	ONE-WAY
14	267+07	269+80	NB RT TL	ONE-WAY
15	270+62	282+26	NB THRU LT	ONE-WAY
4	270+62	273+48	NB THRU RT	ONE-WAY
15	270+62	282+26	SB THRU	ONE-WAY
30	270+62	276+50	SB RT TL	ONE-WAY
33	270+62	277+13	SB LT TL	ONE-WAY
9	283+18	289+66	NB THRU	ONE-WAY
9	283+18	289+66	SB THRU	ONE-WAY
15	283+18	286+13	SB RT TL	ONE-WAY
15	283+18	286+13	SB LT TL	ONE-WAY
31	290+45	315+12	NB THRU	ONE-WAY
31	290+45	315+00	SB THRU	ONE-WAY
3	290+45	290+95	SB LT TL	ONE-WAY
18	311+42	314+98	NB RT TL	ONE-WAY
28	312+34	314+97	NB DUAL LT	ONE-WAY
SPRINGFIELD / HARRISON				
11	24+65	32+72	EB THRU	ONE-WAY
10	24+65	32+54	WB THRU	ONE-WAY
13	30+13	32+77	EB RT TL	ONE-WAY
13	30+13	32+74	EB LT TL	ONE-WAY
26	34+24	39+43	WB RT TL	ONE-WAY
5	34+35	37+94	WB THRU	ONE-WAY
15	34+35	37+33	WB LT TL	ONE-WAY
4	34+51	37+94	EB THRU	ONE-WAY
6	36+71	37+79	EB RT TL	ONE-WAY
3	38+73	41+30	EB THRU	ONE-WAY
3	38+73	41+30	WB THRU	ONE-WAY
SOUTHROCK LANE				
4			EB THRU	ONE-WAY
4			EB RT TL	ONE-WAY
SAUK LANE				
7			EB RT TL	ONE-WAY
AMBER				
IL ROUTE 2				
47	262+95	269+83	MEDAIN	TWO-WAY
91	270+62	281+95	MEDIAN	TWO-WAY
46	283+29	289+69	MEDIAN	TWO-WAY
119	290+45	312+30	MEDIAN	TWO-WAY
SE RAMP				
10	13+85	17+75	LT EDGE	ONE-WAY
SOUTHROCK LANE				
9			MEDIAN	TWO-WAY
SAUK LANE				
12			MEDIAN	TWO-WAY
999	TOTAL			

78200410 GUARDRAIL MARKERS, TYPE A				
EACH	LOCATION	OFFSET		REMARKS
HARRISON AVENUE				
8	36+95.9	40+70.1	LT	50' SPACING
3	39+39.9	40+77.4	RT	50' SPACING
11	TOTAL			

78201000 TERMINAL MARKER - DIRECT APPLIED				
EACH	LOCATION	OFFSET		REMARKS
1	38+90.1		RT	
1	TOTAL			

78300100 PAVEMENT MARKING REMOVAL				
SQ FT	LOCATION	OFFSET		REMARKS
SPRINGFIELD AVENUE				
62	24+65	32+00	EB	
62	24+65	32+00	WB	
124	TOTAL			

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL				
EACH	LOCATION	OFFSET		REMARKS
IL ROUTE 2				
65	253+78	270+00		SOUTHBOUND
82	253+78	270+00		NORTHBOUND
112	270+00	283+00		
74	283+00	287+50		
333	TOTAL			

84200500 REMOVAL OF LIGHTING UNIT, SALVAGE				
EACH	LOCATION	OFFSET		REMARKS
IL ROUTE 2				
1	308+74	38' RT		
1	309+78	41' LT		
1	310+81	44' RT		
1	311+85	45' LT		
1	312+91	56' RT		
1	313+95	44' LT		
1	315+04	70' RT		
1	317+06	46' RT		
1	318+10	55' LT		
1	319+12	44' RT		
1	320+20	42' LT		
1	321+21	42' RT		
1	322+73	36' LT		
1	327+22	38' LT		
HARRISON				
1	34+85	44' RT		
1	35+75	57' LT		
1	36+65	44' RT		
1	37+65	44' LT		
1	38+85	40' RT		
1	39+75	39' LT		
1	40+84	38' RT		
21	TOTAL			

84200804 REMOVAL OF POLE FOUNDATION				
EACH	LOCATION	OFFSET		REMARKS
IL ROUTE 2				
1	308+74	38' RT		
1	309+78	41' LT		
1	310+81	44' RT		
1	311+85	45' LT		
1	312+91	56' RT		
1	313+95	44' LT		
1	315+04	70' RT		
1	317+06	46' RT		
1	318+10	55' LT		
1	319+12	44' RT		
1	320+20	42' LT		
1	321+21	42' RT		
1	322+73	36' LT		
1	327+22	38' LT		
HARRISON				
1	34+85	44' RT		
1	35+75	57' LT		
1	36+65	44' RT		
1	37+65	44' LT		
1	38+85	40' RT		
1	39+75	39' LT		
1	40+84	38' RT		
21	TOTAL			

89502376 REBUILD EXISTING HANDHOLE				
EACH	LOCATION	OFFSET		REMARKS
1	283+14	54' RT		
1	TOTAL			

89502385 REMOVE EXISTING CONCRETE FOUNDATION				
FOOT	LOCATION	OFFSET		REMARKS
1	312+72, 51' LT			
1	TOTAL			

X0322881 TREE TRIMMING				
EACH	LOCATION	OFFSET		REMARKS
1	278+45	73' RT		
1	285+83	62' RT		
2	TOTAL			

X2110100 TOPSOIL FURNISH AND PLACE, SPECIAL				
CU YD	LOCATION	OFFSET		REMARKS
IL ROUTE 2				
806	321+69.75	327+18.79	MEDIAN	
769	331+85.12	337+32.51	MEDIAN	
SPRINGFIELD				
326	24+65	28+04.36	MEDIAN	
1,901	TOTAL			

X4402020 CONCRETE MEDIAN SURFACE REMOVAL				
SQ FT	LOCATION	OFFSET		REMARKS
IL ROUTE 2				
3,275	334+12	337+32.51		
3,275	TOTAL			

FILE NAME =	USER NAME = patsp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAP 742 (IL 2) SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
G:\2010\TRANS\B10701\DDN\Cover and Schedules.dgn	Module\001500-SCHEDULES.dgn	DRAWN -	REVISED -					742	34R	WINNEBAGO	491	46
	PLOT SCALE = 10.0000' / IN.	CHECKED -	REVISED -					CONTRACT NO. 64515			ILLINOIS FED. AID PROJECT	
	PLOT DATE = 2/24/2012	DATE -	REVISED -					SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.