


**LEGEND**

- EXISTING ROADWAY LIGHTPOLE AND LUMINAIRE TO BE REMOVED, SALVAGE
- PROPOSED DECORATIVE LIGHT POLE AND LUMINAIRE ALUMINUM, 40 FT. M.H., PULSE START METAL HALIDE, HORIZONTAL MOUNT 400 WATT (SEE NOTE 13 ON SHEET 301)
- IC — PROPOSED UNDERGROUND CONDUIT, HDPE SDR-11, 1/2" DIA. WITH PULL STRING AND TRACER WIRE
- L — PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA. ROADWAY LIGHTING CASING
- CHH — PROPOSED HANDHOLE PER IDOT STD 814001
- CHH — PROPOSED HANDHOLE, COMPOSITE CONCRETE TYPE AS INDICATED
- PROPOSED UTILITY POLE (BY OTHERS)
- PROPOSED LIGHTING CONTROLLER, 100 AMP, 480V
- HH = PROPOSED HANDHOLE PER IDOT STD 814001
- CHH = PROPOSED HANDHOLE, COMPOSITE CONCRETE TYPE AS INDICATED
- PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, BORED AND PULLED, SIZE AND CONDUCTORS AS INDICATED.
- L — PROPOSED UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1/4" DIA. POLYETHYLENE
- FO — PROPOSED UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA. WITH PULL STRING AND TRACER WIRE
- PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, SIZE AND CONDUCTORS AS INDICATED

**NOTES:**

1. REFER TO ROADWAY LIGHTING NOTES ON SHEET 301.
2. SEE "HANDHOLE, COMPOSITE CONCRETE" SPECIAL PROVISION FOR HANDHOLE SIZES.
3. CONNECTION INTO THE EXISTING IDOT HANDHOLE SHALL BE INCIDENTAL AND INCLUDED IN THE COST FOR UNDERGROUND CONDUIT.



USER NAME = Jason Dove  
 FILE NAME = 0264515-shr-light106.dgn  
 PLOT SCALE = 20.0000' / 1" =  
 PLOT DATE = 4/18/2012 - 7:00:48 PM

DESIGNED - AS	REVISED - 04/17/2012
DRAWN - JWD	REVISED -
CHECKED - AB	REVISED -
DATE - 01/25/2012	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**ROADWAY LIGHTING PLAN  
 F.A.P. 742 (IL RTE 2)**

SCALE: 1" = 20'    SHEET 6 OF 20 SHEETS    STA. 330+00 TO STA. 336+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	34R	WINNEBAGO	491	306
CONTRACT NO. 64515				
ILLINOIS FED. AID PROJECT				

DIRECTORY = L:\PROJECTS\1126004\1126004-01-ACADD\Sheets\026-015-Missouri\