

PAY ITEM #	DESCRIPTION	UNITS	TOTAL QUANTITY	100% STATE	
				WINNEBAGO CO.	BODNE CO.
				101-0154/0158 0014	004-0013 0014
42001300	PROTECTIVE COAT	SQ YD	76.7	38	38.7
44004250	PAVED SHOULDER REMOVAL	SQ YD	242.1		242.1
50102400	CONCRETE REMOVAL	CU YD	21.7	6.8	14.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	21.6	6.6	15
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2810	1150	1660
50800515	BAR SPLICERS	EACH	40	16	24
52000110	PREFORMED JOINT STRIP SEAL	FOOT	269	167	102
67100100	MOBILIZATION	LSUM	1	0.5	0.5
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	LSUM	1	1	
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2	2	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1		1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1		1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	EACH	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8	4	4
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	516	240	276
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	22733	14511	8222
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	48		48
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6255.5	4837.1	1418.4
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1748.3	1076.9	671.4
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1748.3	1076.9	671.4
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	12709	4000	8709
* 78001130	PAINT PAVEMENT MARKING-LINE 6"	FOOT	450	450	
* 78001150	PAINT PAVEMENT MARKING-LINE 12"	FOOT	562		562
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	374	374	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2744.5	1012	1732.5
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	21	21	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2
Z0012754	STRUCTURAL REPAIR OF CONCRETE LESS THAN OR EQUAL TO 5 INCHES	SQ FT	0.5	0.5	
Z0062456	TEMPORARY PAVEMENT	SQ YD	1629	907	722

\* SPECIALTY ITEM

FILE NAME =  
C:\Joint Repair\_64H75\64H75\_PLA\HJdn

USER NAME * 10009	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE * 1/4" = 1' / in.	CHECKED -	REVISED -
PLOT DATE * Thu Apr 05 09:38:39 2012	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	(1B, 1BR, 1BR-2R)M	VARIOUS	31	4
CONTRACT NO. 64H75			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	

Rev