

78001110 PAINT PAVEMENT MARKING -LINE 4"

IL-251	FOOT	REMARK
	4000	EOP SB&NB
BR 20		
STA 261+82.5 TO STA 268+88.0	4075.6	PAINTED MEDIAN
STA 268+88.0 TO STA 276+02.6	1789.2	CENTERLINE (SB SKIPS-NB SOLID)
STA 267+22.5 TO STA 274+39.6	1434.2	SB EOP (WHITE)
STA 267+37.5 TO STA 274+42.6	1410.2	NB EOP (WHITE)

TOTAL 12709.2

78001130 PAINT PAVEMENT MARKING-LINE 6"

IL-251	FOOT	REMARK
STA 223+26.4 TO STA 227+26.4	200	NB SKIP-DASH
STA 210+44.9 TO STA 215+44.9	250	SB SKIP-DASH

TOTAL 450

78001150 PAINT PAVEMENT MARKING-LINE 12"

BR 20	FOOT	REMARK
STA 261+82.5 TO STA 268+88.0	562	PAINTED MEDIAN

TOTAL 562

78100200 TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER

IL-251	EACH	REMARK
STA 215+13.9 TO STA 217+22.8	9	STAGE 1 NB (YELLOW)
STA 220+60.3 TO STA 233+86.4	54	STAGE 1 NB (YELLOW)
STA 215+40.6 TO STA 222+99.8	31	STAGE 1 NB (WHITE)
STA 203+84.4 TO STA 217+63.3	56	STAGE 1 SB (YELLOW)
STA 221+40.4 TO STA 223+57.4	10	STAGE 1 SB (YELLOW)
STA 215+71.6 TO STA 223+30.7	31	STAGE 1 SB (WHITE)
STA 215+49.3 TO STA 217+27.8	8	STAGE 2 NB (WHITE)
STA 221+13.8 TO STA 233+86.4	52	STAGE 2 NB (WHITE)
STA 215+56.3 TO STA 223+12.8	31	STAGE 2 NB (YELLOW)
STA 203+84.4 TO STA 216+64.9	52	STAGE 2 SB (WHITE)
STA 221+40.4 TO STA 223+22	8	STAGE 2 SB (WHITE)
STA 215+44.9 TO STA 223+15.1	32	STAGE 2 SB (YELLOW)

TOTAL 374

78300100 PAVEMENT MARKING REMOVAL

IL-251	SQ FT	REMARK
IL-251 PRE STAGE		
STA 223+03 TO STA 215+46.5	253.0	NB LT EXISTING EOP
STA 215+68.3 TO STA 223+24.5	253.0	SB LT EXISTING EOP
	506.0	

IL-251 STAGE 1	SQ FT	REMARK
STA 223+03 TO STA 215+46.5	253.0	NB RT EXISTING EOP
STA 215+68.3 TO STA 223+24.5	253.0	SB RT EXISTING EOP
	506.0	

BR 20	SQ FT	REMARK
STA 26182.5 TO STA 268+88.0	960.3	PAINTED MEDIAN
STA 268+88.0 TO STA 276+02.6	298.2	CENTER LINE
STA 267+22.5 TO STA 274+39.6	239.0	SB EOP
STA 267+50.1 TO STA 274+39.6	235.0	NB EOP
	1732.5	

TOTAL 2744.5

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

IL-251	EACH	REMARKS
STA 222+89	1	NB STAGE 1
STA 215+82.3	1	SB STAGE 1
BR 20		
STA 267+32.0	1	STAGE 1
STA 274+31.5	1	STAGE 1

TOTAL 4

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

IL-251	EACH	REMARKS
STA 222+89	1	NB STAGE 2
STA 215+82.3	1	SB STAGE 2
BR 20		
STA 267+32.0	1	STAGE 2
STA 274+31.5	1	STAGE 2

TOTAL 4

Z0062456 TEMPORARY PAVEMENT

IL-251	SQ YDS	REMARKS
IL-251 PRE STAGE		
STA 220+38.9 TO STA 222+99.8	145.0	NB RT SHLD
STA 215+40.6 TO STA 217+89.9	138.5	NB RT SHLD
STA 215+71.6 TO STA 218+32.5	145.0	SB RT SHLD
STA 220+81.4 TO STA 223+30.7	138.5	SB RT SHLD
	567.0	

IL-251 STAGE 1	SQ YDS	REMARKS
STA 220+56.6 TO STA 223+12.8	85.3	NB LT SHLD
STA 215+56.3 TO STA 218+10.1	84.7	NB LT SHLD
STA 215+44.9 TO STA 218+01.1	85.3	SB LT SHLD
STA 220+61.3 TO STA 223+15.1	84.7	SB LT SHLD
	340.0	

BR 20	SQ YDS	REMARKS
STA 266+99.3 TO STA 268+67.1	188.7	STAGE 1
STA 272+59 TO STA 274+52.5	215	STAGE 1
STA 267+12.5 TO STA 269+01	209.4	STAGE 2
STA 272+93 TO STA 274+67.6	109	STAGE 2
	722.1	

TOTAL 1629.1

FILE NAME = Cr:Joint Repair_84H75\84H75.PLAN.dgn	USER NAME = icara	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	VAR.	(1B, 1BR, 1BR-2RJM)	VARIOUS	31	6
		CHECKED -	REVISED -					CONTRACT NO. 84H75				
		DATE	REVISED		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							