



- A** REMOVE: 32' GATE
REPLACEMENT: 6'x20' CHAIN LINK GATE, DOUBLE (SPECIAL)
- B** INSTALL 6'x20' CHAIN LINK GATE, DOUBLE (SPECIAL)
- C** REMOVE: 9' GATE
REPLACEMENT: 6'x9' CHAIN LINK GATE, SINGLE (SPECIAL)
- D** REMOVE: 16' GATE
REPLACEMENT: 6'x8' CHAIN LINK GATE, DOUBLE (SPECIAL)

LEGEND

- x - x - x - EXISTING WOVEN WIRE FENCE
- EXISTING POWER POLE
- ⊗ RIGHT OF WAY MARKER
- ⊞ TELEPHONE PEDESTAL
- x / \ x - PROPOSED CHAIN LINK GATE
- x - x - x - PROPOSED CHAIN LINK FENCE

GENERAL NOTES

THE CONTRACTOR SHALL CONSULT THE DEPARTMENT'S BRIDGE ENGINEER FOR EXACT LOCATION OF FENCE INSTALLATION PRIOR TO BEGINNING FENCE REMOVAL OPERATIONS.

PLAN DIMENSIONS SHALL BE VERIFIED IN THE FIELD PRIOR TO ORDERING OF MATERIALS.

FILE NAME =	USER NAME = potelyj	DESIGNED - TIM PLETSCH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SITE PLAN FOR BRIDGE MAINTENANCE HEADQUARTERS	F.A.I. F.A.P.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
01\pwwork\pwwork\potelyj\d0262107\03665669-shd-details.dgn		DRAWN - TIM PLETSCH	REVISED -			80	D3 FENCE REPAIR 2012-1	LASALLE	7	4	
PLOT SCALE = 1/8" = 100'-0"		CHECKED - RON WOODSHANK	REVISED -			CONTRACT NO. 66B69					
PLOT DATE = 2/16/2012		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
				SCALE:	SHEET 1 OF 1 SHEETS	STA.	TO STA.				