

IMPACT ATTENUATOR SCHEDULE					
LOCATION			ATTENUATOR	SUBBASE	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3
			BASE	GRANULAR MAT, TY. B 4"	
NO.	MP	STRUCTURE NO.	SO YD	SO YD	EACH
BUREAU COUNTY					
1	1.02	MEDIAN SIGN TRUSS	55	73	2.0
2	1.35	MEDIAN SIGN TRUSS	55	73	2.0
3	1.6	PIER	55	73	2.0
4	2.6	PIER	55	73	2.0
5	5.35	PIER	55	73	2.0
6	8.9	MEDIAN SIGN TRUSS	55	73	2.0
7	9.3	PIER	55	73	2.0
8	9.64	MEDIAN SIGN TRUSS	55	73	2.0
9	11.4	MEDIAN SIGN TRUSS	55	73	2.0
TOTALS			492	660	18

SEEDING AND EROSION CONTROL											
LOCATION			SQ YD	SEEDING,	NITROGEN	PHOSPHORUS	POTASSIUM	EROSION	TEMPORARY	TEMPORARY	PERIMETER
				CLASS 2	FERTILIZER	FERTILIZER	FERTILIZER	CONTROL	EROSION CONTROL	DITCH	EROSION
NO.	MP	STRUCTURE NO.	ACRE	NUTRIENT	NUTRIENT	NUTRIENT	NUTRIENT	BLANKET	SEEDING	CHECKS	BARRIER
BUREAU COUNTY				POUND	POUND	POUND	POUND	SO YD	POUND	FOOT	FOOT
1	1.02	MEDIAN SIGN TRUSS	3556	0.73	66	66	66	3556	73	12	500
2	1.35	MEDIAN SIGN TRUSS	3556	0.73	66	66	66	3556	73	12	500
3	1.6	PIER	3556	0.73	66	66	66	3556	73	12	500
4	2.6	PIER	3556	0.73	66	66	66	3556	73	12	500
5	5.35	PIER	3556	0.73	66	66	66	3556	73	12	500
6	8.9	MEDIAN SIGN TRUSS	3556	0.73	66	66	66	3556	73	12	500
7	9.3	PIER	3556	0.73	66	66	66	3556	73	12	500
8	9.64	MEDIAN SIGN TRUSS	3556	0.73	66	66	66	3556	73	12	500
9	11.4	MEDIAN SIGN TRUSS	3556	0.73	66	66	66	3556	73	12	500
TOTALS				6.6	594	594	594	32004	657	108	4500

EARTHWORK SCHEDULE						
LOCATION			EARTH EXCAVATION (CUTS)	EARTH EXCAVATION ADJ FOR SHRINKAGE 25%	EMBANKMENT (FILLS)	(FURNISHED EX.)
						EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
NO.	MP	STRUCTURE NO.	CU YD	CU YD	CU YD	CU YD
BUREAU COUNTY						
1	1.02	MEDIAN SIGN TRUSS	19.4	14.5	310.3	-295.8
2	1.35	MEDIAN SIGN TRUSS	12.1	9.1	176.3	-167.2
3	1.6	PIER	10.3	7.7	95.3	-87.6
4	2.6	PIER	0.0	0.0	133.0	-133.0
5	5.35	PIER	2.5	1.9	152.0	-150.1
6	8.9	MEDIAN SIGN TRUSS	2.5	1.9	402.5	-400.6
7	9.3	PIER	35.9	26.9	46.3	-19.4
8	9.64	MEDIAN SIGN TRUSS	0.0	0.0	646.0	-646.0
9	11.4	MEDIAN SIGN TRUSS	3.5	2.6	382.6	-380.0
TOTALS			86.2			-2279.7
			PAY ITEM			PAY ITEM

CRASHWALL EXTENSIONS				
LOCATION			CONCRETE STRUCTURES	REINFORCEMENT
				BARS
NO.	MP	STRUCTURE NO.	CU YD	EPOXY COATED POUND
BUREAU COUNTY				
1	1.02	MEDIAN SIGN TRUSS		
2	1.35	MEDIAN SIGN TRUSS		
3	1.6	PIER		
4	2.6	PIER	7.4	760
5	5.35	PIER		
6	8.9	MEDIAN SIGN TRUSS		
7	9.3	PIER		
8	9.64	MEDIAN SIGN TRUSS		
9	11.4	MEDIAN SIGN TRUSS		
TOTALS			7.4	760