

SEEDING AND EROSION CONTROL											
LOCATION			SQ YD	SEEDING,	NITROGEN	PHOSPHORUS	POTASSIUM	EROSION	TEMPORARY	TEMPORARY	PERIMETER
NO.	MP	STRUCTURE NO.		CLASS 2	FERTILIZER	FERTILIZER	FERTILIZER	CONTROL	EROSION CONTROL	DITCH	EROSION
			ACRE	NUTRIENT	NUTRIENT	NUTRIENT	NUTRIENT	BLANKET	SEEDING	CHECKS	BARRIER
				POUND	POUND	POUND	POUND	SO YD	POUND	FOOT	FOOT
LASALLE COUNTY											
1	57.3	MEDIAN SIGN TRUSS	4644	0.96	86	86	86	4644	96	12	500
2	57.8, 57.81	050-0194 & SIGN TRUSS	4644	0.96	86	86	86	4644	96	12	500
3	58.3	MEDIAN SIGN TRUSS	4644	0.96	86	86	86	4644	96	12	500
4	59.2	MEDIAN SIGN TRUSS	4644	0.96	86	86	86	4644	96	12	500
5	59.6	MEDIAN SIGN TRUSS	4644	0.96	86	86	86	4644	96	12	500
6	59.8	050-0176	4644	0.96	86	86	86	4644	96	12	500
7	60.3	MEDIAN SIGN TRUSS	4644	0.96	86	86	86	4644	96	12	500
8	61.2	MEDIAN SIGN TRUSS	4644	0.96	86	86	86	4644	96	12	500
9	61.8	050-0175	4644	0.96	86	86	86	4644	96	12	500
10	64.9	050-0172	4644	0.96	86	86	86	4644	96	12	500
11	65.9	050-0171	4644	0.96	86	86	86	4644	96	12	500
12	68.25	050-0181	4644	0.96	86	86	86	4644	96	12	500
13	70.8	050-0166	4644	0.96	86	86	86	4644	96	12	500
14	71.85	050-0165	4644	0.96	86	86	86	4644	96	12	500
15	74.85	050-0162	4644	0.96	86	86	86	4644	96	12	500
TOTALS				14.4	1290	1290	1290	69667	1440	180	7500

EARTHWORK SCHEDULE						
LOCATION			EARTH	EARTH EXCAVATION	EMBANKMENT	(FURNISHED EX.)
NO.	MP	STRUCTURE NO.	EXCAVATION	ADJ FOR SHRINKAGE	(FILLS)	EARTHWORK
			(CUTS)	25%		BALANCE WASTE
			CU YD	CU YD	CU YD	(+) OR SHORTAGE (-)
LASALLE COUNTY						
1	57.3	MEDIAN SIGN TRUSS	17.9	13.4	303.3	-289.9
2	57.8, 57.81	050-0194 & SIGN TRUSS	57.9	43.4	234.4	-191.0
3	58.3	MEDIAN SIGN TRUSS	21.9	16.4	326.9	-310.5
4	59.2	MEDIAN SIGN TRUSS	51.9	38.9	256.4	-217.5
5	59.6	MEDIAN SIGN TRUSS	38.7	29.0	158.8	-129.8
6	59.8	050-0176	12.5	9.4	27.8	-18.4
7	60.3	MEDIAN SIGN TRUSS	39.4	29.6	114.9	-85.4
8	61.2	MEDIAN SIGN TRUSS	61.9	46.4	67.0	-20.6
9	61.8	050-0175	72.8	54.6	32.6	22.0
10	64.9	050-0172	8.1	6.1	118.9	-112.8
11	65.9	050-0171	18.3	13.7	107.8	-94.1
12	68.25	050-0181	14.1	10.6	145.5	-134.9
13	70.8	050-0166	15.6	11.7	143.2	-131.5
14	71.85	050-0165	7.2	5.4	161.1	-155.7
15	74.85	050-0162	59.9	44.9	99.4	-54.5
TOTALS			498.1			-1924.4
			PAY ITEM			PAY ITEM

IMPACT ATTENUATOR SCHEDULE					
LOCATION			ATTENUATOR	SUBBASE	IMPACT ATTENUATORS
NO.	MP	STRUCTURE NO.	BASE	GRANULAR	(NON-REDIRECTIVE)
			SQ YD	MAT, TY. B 4"	TEST LEVEL 3
				SQ YD	EACH
LASALLE COUNTY					
1	57.3	MEDIAN SIGN TRUSS	55	73	2.0
2	57.8, 57.81	050-0194 & SIGN TRUSS	55	73	2.0
3	58.3	MEDIAN SIGN TRUSS	55	73	2.0
4	59.2	MEDIAN SIGN TRUSS	55	73	2.0
5	59.6	MEDIAN SIGN TRUSS	55	73	2.0
6	59.8	050-0176	55	73	2.0
7	60.3	MEDIAN SIGN TRUSS	55	73	2.0
8	61.2	MEDIAN SIGN TRUSS	55	73	2.0
9	61.8	050-0175	55	73	2.0
10	64.9	050-0172	55	73	2.0
11	65.9	050-0171	55	73	2.0
12	68.25	050-0181	55	73	2.0
13	70.8	050-0166	55	73	2.0
14	71.85	050-0165	55	73	2.0
15	74.85	050-0162	55	73	2.0
TOTALS			819	1100	30

CRASHWALL EXTENSIONS				
LOCATION			CONCRETE	REINFORCEMENT
NO.	MP	STRUCTURE NO.	STRUCTURES	BARS
			CU YD	EPOXY COATED
				POUND
LASALLE COUNTY				
1	57.8, 57.81	050-0194 & SIGN TRUSS	2.1	330
2	59.8	050-0176	3.1	330
3	61.8	050-0175	4.0	410
4	64.9	050-0172	3.0	350
5	65.9	050-0171	5.6	920
6	68.25	050-0181	3.0	460
7	70.8	050-0166	2.1	260
8	71.85	050-0165	9.2	1000
9	74.85	050-0162	2.1	260
TOTALS			34.2	4320

FILE NAME = USER NAME = ferguson
 es:\pwwork\pwwork\ferguson\0294370\066B99-shr-schedule.dgn
 PLOT SCALE = 100.0000' / in.
 PLOT DATE = 3/30/2012

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

QUANTITY SCHEDULES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE. SECTION COUNTY TOTAL SHEET NO.
 39 03 IMPACT ATTENUATOR 2012-2 LASALLE 94 4
 CONTRACT NO. 66B99
 ILLINOIS FED. AID PROJECT