

SEEDING										
LOCATION		SQ YD	25000210	25000400	25000500	25000600	25100630	28000250	28000305	28000400
			SEEDING,	NITROGEN	PHOSPHORUS	POTASSIUM	EROSION	TEMPORARY	TEMPORARY	PERIMETER
			CLASS 2A	FERTILIZER	FERTILIZER	FERTILIZER	CONTROL	EROSION CONTROL	DITCH	EROSION
MP	STRUCTURE NO.		ACRE	POUND	POUND	POUND	SQ YD	POUND	FOOT	FOOT
LIVINGSTON COUNTY										
188.5	053-0119	4444.4	0.92	55.10	55.10	55.10	4444.4	92.0	12.0	400.0
191.3	053-0122	4444.4	0.92	55.10	55.10	55.10	4444.4	92.0	12.0	400.0
193	42" FOUNDATION NB	111.1	0.03	1.38	1.38	1.38	111.1	3.0	0.0	50.0
194	42" FOUNDATION SB	111.1	0.03	1.38	1.38	1.38	111.1	3.0	0.0	50.0
198.2	053-0130	4444.4	0.92	55.10	55.10	55.10	4444.4	92.0	12.0	400.0
203.6	053-0135	4444.4	0.92	55.10	55.10	55.10	4444.4	92.0	12.0	400.0
208	053-0113	4444.4	0.92	55.10	55.10	55.10	4444.4	92.0	12.0	400.0
209	053-0138	4444.4	0.92	55.10	55.10	55.10	4444.4	92.0	12.0	400.0
210.1	053-0112	4444.4	0.92	55.10	55.10	55.10	4444.4	92.0	12.0	400.0
214.9	053-0141 MEDIAN	4444.4	0.92	55.10	55.10	55.10	4444.4	92.0	12.0	200.0
214.9	053-0141 NB RT	1111.1	0.23	13.78	13.77	13.77	1111.1	23.0	6.0	400.0
217	053-0114	4444.4	0.92	55.10	55.10	55.10	4444.4	92.0	12.0	400.0
LIVINGSTON COUNTY TOTALS			9.00	513	513	513	41334	857	114	3900
GRUNDY COUNTY										
218.9	032-0077	4444.4	0.92	55.1	55.1	55.1	4444.4	92.0	12.0	400.0
219.9	032-0079	4444.4	0.92	55.1	55.1	55.1	4444.4	92.0	12.0	400.0
224.3	032-0078 MEDIAN	4444.4	0.92	55.1	55.1	55.1	4444.4	92.0	12.0	400.0
224.3	032-0078 NB RT	1111.1	0.23	13.8	13.8	13.8	1111.1	23.0	6.0	200.0
GRUNDY COUNTY TOTALS			3.00	180	180	180	14445	299	42	1400
TOTALS			12.00	693	693	693	55779	1156	156	5300

EARTHWORK SCHEDULE					
LOCATION		EARTH	EARTH EXCAVATION	EMBANKMENT	EARTHWORK
		EXCAVATION	ADJ FOR SHRINKAGE	(FILLS)	BALANCE WASTE
MP	STRUCTURE NO.	(CUTS)	25%	(FILLS)	(+) OR SHORTAGE (-)
		CU YD	CU YD	CU YD	CU YD
LIVINGSTON COUNTY					
188.5	053-0119	9.6	7.2	116.6	-109.4
191.3	053-0122	16.4	12.3	94.8	-82.5
198.2	053-0130	17.7	13.3	30.5	-17.2
203.6	053-0135	16.9	12.7	27.5	-14.8
208	053-0113	11.8	8.8	15.1	-6.3
209	053-0138	19.8	14.9	19.2	-4.3
210.1	053-0112	5.7	4.3	53.2	-48.9
214.9	053-0141 MEDIAN	23.6	17.7	69.3	-51.6
214.9 RT	053-0141 NB RT	1.5	1.1	12.4	-11.3
217	053-0114	13.9	10.4	26.5	-16.1
LIVINGSTON COUNTY TOTALS		137	103	465	-363
GRUNDY COUNTY					
218.9	032-0077	42.3	31.7	74.8	-43.1
219.9	032-0079	12.8	9.6	121.1	-111.5
224.3	032-0078 MEDIAN	12.4	9.3	179.3	-170.0
224.3 RT	032-0078 NB RT	8.9	5.2	28.4	-23.2
GRUNDY COUNTY TOTALS		75	56	404	-348
TOTALS		212	159	869	-711

CRASHWALL EXTENSION				
LOCATION		50102400	50300225	50800205
		CONCRETE	CONCRETE	REINFORCEMENT
MP	STRUCTURE NO.	REMOVAL	STRUCTURES	BARS,
		CU YD	CU YD	EPOXY COATED
				POUND
LIVINGSTON COUNTY				
188.5	053-0119		10.5	920.0
191.3	053-0122 (SOLID PIER)			
196.6	053-0116		18.8	1750.0
198.2	053-0130		7.8	590.0
200.5	053-0115		12.6	1350.0
203.6	053-0135		3.7	380.0
208.0	053-0113		5.1	410.0
209.0	053-0138		14.9	1320.0
210.1	053-0112		8.6	680.0
214.9	053-0141 NB RT, PIER#2		6.3	470.0
214.9	053-0141 MEDIAN, PIER#1		7.8	570.0
217.0	053-0114		16.5	1430.0
LIVINGSTON COUNTY TOTALS		0.0	112.6	9870
GRUNDY COUNTY				
218.9	032-0077		3.8	380.0
219.9	032-0079		19.2	1820.0
224.3	032-0078 MEDIAN, PIER#3		4.6	400.0
224.3	032-0078 NB RT, PIER#2		4.5	400.0
226.9	032-0093		11.7	1180.0
228.7	032-0092	3.6	9.6	850.0
231.0	032-0090	3.8	10.2	900.0
233.2	032-0091	6.1	15.4	1390.0
GRUNDY COUNTY TOTALS		13.5	79.0	7320
TOTALS		13.5	191.6	17190