

GENERAL NOTES

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

ONLY THOSE TREES DESIGNATED BY THE ENGINEER OR LISTED IN THE TREE REMOVAL SCHEDULE SHALL BE REMOVED. THE CONTRACTOR SHALL PROTECT ALL REMAINING TREES FROM DAMAGE DUE TO HIS OPERATIONS.

THE FINISHED EARTHWORK SHALL HAVE A VEGETATION SUSTAINING SOIL COVERING THE TOP FOUR INCHES ( 100 MILLIMETERS) IN AREAS TO BE SEEDED OR SODDED. THE VEGETATION SUSTAINING SOIL REQUIRED WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF FRURNISHED EXCAVATION.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

SUMMARY OF QUANTITIES

CODE NO	ITEM	CONSTRUCTION TYPE CODE:		0021	0021
		UNIT	TOTAL QTY <i>90% F.E.D. / 10% STATE</i>	GRUNDY COUNTY	LIVINGSTON COUNTY
20400800	FURNISHED EXCAVATION	CU YD	155	155	
* 25000210	SEEDING, CLASS 2A	ACRE	0.7	0.7	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	60	60	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	60	60	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	60	60	
* 25100115	MULCH, METHOD 2	ACRE	0.7	0.7	
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	134	134	
* 28000305	TEMPORARY DITCH CHECKS	FOOT	60	60	
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	12	8	4
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	0.5	0.5
78202000	TERMINAL MARKER - POST MOUNTED	EACH	5	4	1
X0325231	CABLE GUARD MARKER	EACH	1713	1320	393
Z0029652	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	68514	52804	15710
Z0029653	HIGH TENSION CABLE MEDIAN BARRIER DEMONSTRATION	EACH	2	1	1
Z0029654	HIGH TENSION CABLE MEDIAN BARRIER TERMINALS	EACH	36	28	8
X0326867	RADAR SPEED TRAILER	CAL MO	1	0.5	0.5
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	160	80	80
X0326907	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	CAL MO	2	1	1
X7010805	TRAFFIC CONTROL AND PROTECTION, STANDARD. 701401 (SPECIAL)	L SUM	1	0.5	0.5

\* SPECIALTY ITEMS

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
DISTRICT THREE

PREPARED BY: Dale Prorok  
DISTRICT STUDIES & PLANS ENGINEER

DATE: \_\_\_\_\_

EXAMINED BY: Arlo Johnson  
DISTRICT CONSTRUCTION ENGINEER

Wayne J. Phillips  
DISTRICT MATERIALS ENGINEER

Robert A. Scheraga  
DISTRICT OPERATIONS ENGINEER

\*D3 Interstate Cable Median Barrier 2012

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	DRAWN -	REVISED -	55			*	GRUNDY, LIV.	15	2	
PLOT SCALE = *SCALE*	CHECKED -	REVISED -	CONTRACT NO. 66C05							
PLOT DATE = *DATE*	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							

SCALE: \_\_\_\_\_ SHEET NO. \_\_\_ OF \_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_