

HIGH TENSION CABLE MEDIAN BARRIER SCHEDULE					
LOCATION	HIGH TENSION CABLE MEDIAN BARRIER	HIGH TENSION CABLE MEDIAN BARRIER	CABLE GUARD MARKERS	HIGH TENSION CABLE MEDIAN BARRIER TERMINALS	TERMINAL MARKER-POST MOUNTED
	SOUTHBOUND	NORTHBOUND	EACH	EACH	EACH
GRUNDY COUNTY					
STA 1105+78 TO STA 1159+20.49	5,342		134	2	1
STA EQ. STA 1159+20.49 (BK)=STA. 752+28.72 (AH)					
STA 1159+70 HTC OVERLAP					
STA 752+28.72 TO STA 714+05	3,874		97	2	
STA 713+45 CENTER OF MAINTENANCE X-OVER					
STA 713+45 TO STA 680+07	3,338		83	2	1
STA 680+57 HTC OVERLAP					
STA 680+57 TO STA 647+18	3,339		83	2	
STA 647+68 HTC OVERLAP					
STA 647+68 TO STA 594+88	5,280		132	2	
STA 595+38 HTC OVERLAP					
STA 595+38 TO STA 542+58	5,280		132	2	
STA 543+08 HTC OVERLAP					
STA 543+08 TO STA 490+28	5,280		132	2	
STA 490+78 HTC OVERLAP					
STA 490+78 TO STA 444+50	4,628		116	2	
STA 444+00 TO STA 440+00		400	10	2	
SN 032-0082					
STA 439+00 TO 452+39	1,339		33	2	
STA 451+94 CENTER OF MAINTENANCE X-OVER					
STA 451+46 TO STA 398+66	5,280		132	2	1
STA 399+16 HTC OVERLAP					
STA 399+16 TO STA 346+36	5,280		132	2	
STA 346+86 HTC OVERLAP					
STA 346+86 TO STA 309+86	3,700		93	2	
STA 309+38 CENTER OF MAINTENANCE X-OVER					
STA 308+90 TO STA 304+46	444		11	2	1
GRUNDY COUNTY TOTAL	52,404	400	1,320	28	4
LIVINGSTON COUNTY					
STA 304+46 TO STA 270+00	3,446		86	2	
STA 269+50 TO STA 265+50		400	10	2	
SN 053-0144					
STA 264+50 TO STA 193+70	7,080		177	2	
STA 193+22 CENTER OF MAINTENANCE X-OVER					
STA 192+74 TO STA 144+90	4,784		120	2	1
LIVINGSTON COUNTY TOTAL	15,310	400	393	8	1
GRAND TOTAL	67,714	800	1,713	36	5

STA EQ. STA 1159+20.49 (BK)=STA. 752+28.72 (AH)

EARTHWORK SCHEDULE		
STA TO STA	LANE	FURNISHED EXCAVATION
		CU YD
HIGH TENSION CABLE BARRIER		
STA 1106+38 TO STA 1107+38	MEDIAN	6
STA 1109+38 TO STA 1114+38	MEDIAN	98
STA 1119+34 TO STA 1120+38	MEDIAN	7
STA 1121+34 TO STA 1123+34	MEDIAN	5
STA 1149+18 TO STA 1153+26	MEDIAN	39
GRAND TOTALS (ALL GRUNDY COUNTY)		155

SEEDING SCHEDULE									
LOCATION	LANE	LENGTH	SEEDING CLASS 3	NITROGEN FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	MULCH, METHOD 2	TEMP DITCH CHECKS	TEMP EROSION CONTROL SEEDING
			FOOT	ACRE	POUND	POUND	POUND	ACRE	FOOT
CABLE BARRIER AREA									
STA 1106+38 TO STA 1107+38	MEDIAN	100	0.06	5	5	5	0.06		11
STA 1110+38 TO STA 1114+38	MEDIAN	400	0.22	20	20	20	0.22	30	44
STA 1119+34 TO STA 1120+38	MEDIAN	104	0.06	5	5	5	0.06		11
STA 1121+34 TO STA 1123+34	MEDIAN	200	0.11	10	10	10	0.11		22
STA 1149+18 TO STA 1153+26	MEDIAN	408	0.22	20	20	20	0.22	30	45
GRAND TOTAL(ALL GRUNDY COUNTY)			0.7	60	60	60	0.7	60.0	134

*03 Interstate Cable Median Barrier 2012

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -					55	*	GRUNDY, LIV.	15	4	
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -					SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____			CONTRACT NO. 66C05		
	PLOT DATE = #DATE#	DATE -	REVISED -								[ILLINOIS] FED. AID PROJECT		