

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS 100% STATE STRUCTURE 0014 RURAL
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3472	3472
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	108	108
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1362	1362
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	6265	6265
78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	990	990
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	84	84
78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	108	108
78300100	PAVEMENT MARKING REMOVAL	SQ FT	800	800
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	1795	1795
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	16	16
Z0001905	STRUCTURAL STEEL REPAIR	POUND	2400	2400
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1195	1195
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	372	372
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE 1)	SQ YD	10	10
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	50	50

• SPECIALTY ITEMS

FILE NAME =	USER NAME = carpenterd	DESIGNED - RLW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.S. RTE. 2247	SECTION 06-1HB-211-2	COUNTY	TOTAL SHEETS 22	SHEET NO. 4	
c:\pwwork\pwwork\carpenterd\10299254\	D366C16-sht-details.dgn	DRAWN - RLW	REVISED -			SCALE:	SHEET 1 OF 1 SHEETS	STA.	TO STA.	BUREAU	CONTRACT NO. 66C16
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -								
	PLOT DATE = 4/5/2012	DATE -	REVISED -								

ILLINOIS FED. AID PROJECT