

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				IROQUOIS CO.	
				ROADWAY 0005 RURAL	ROADWAY 0005 URBAN
20200100	EARTH EXCAVATION	CU YD	9	8	1
20400800	FURNISHED EXCAVATION	CU YD	39	32	7
25000200	SEEDING, CLASS 2	ACRE	0.14	0.11	0.03
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	14	11	3
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	14	11	3
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	14	11	3
25100630	EROSION CONTROL BLANKET	SQ YD	702	572	130
25200110	SODDING, SALT TOLERANT	SQ YD	55	53	2
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13975	11700	2275
40600300	AGGREGATE (PRIME COAT)	TON	218	183	35
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	31.5	26.3	5.2
40600725	POLYMERIZED LEVELING BINDER (HAND METHOD), N50	TON	52	44	8
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75, N50	TON	4390	3682	708
40600895	CONSTRUCTING TEST STRIP	EACH	2	1.7	0.3

80% FED.  
20% STATE

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = carpenterdj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
o:\pv_work\p\idot\carpenterdj\40302301\366C27-sht-500-schedule.dgn	DRAWN -	REVISED -	317			20 RS-6	IROQUOIS	14	3		
PLOT SCALE = 50.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 66C27								
PLOT DATE = 3/22/2012	DATE -	REVISED -	ILLINOIS FED. AID PROJECT								
						SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____			