

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				PEORIA COUNTY	
				80% FED.	
				20% STATE	
				0004 URBAN	
X 25100115	MULCH, METHOD 2	ACRE	11.4	11.4	
25100630	EROSION CONTROL BLANKET	SQ YD	89	89	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1140	1140	
28000305	TEMPORARY DITCH CHECKS	FOOT	297	297	
28000400	PERIMETER EROSION BARRIER	FOOT	4568	4568	
28000500	INLET AND PIPE PROTECTION	EACH	6	6	
28100825	STONE DUMPED RIPRAP, CLASS B3	TON	1313	1313	
28200200	FILTER FABRIC	SQ YD	1692	1692	
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	7502	7502	
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	7502	7502	
35102600	AGGREGATE BASE COURSE, TYPE B 14"	SQ YD	287	287	
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	2770	2770	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	0.4	0.4	
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	6416	6416	

X SPECIALTY ITEMS

FILE NAME =
D468A38-shr-plan.dgn

USER NAME = ccaustnjs
PLOT SCALE = 100.0000' / in.
PLOT DATE = 3/19/2012

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
318	(72-6)R	PEORIA	117	5
CONTRACT NO. 68A30			ILLINOIS FED. AID PROJECT	