

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				PEORIA COUNTY	
				80% FED.	
				20% STATE	
				0004 URBAN	
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER		EACH	68	68
X 78200410	GUARDRAIL MARKERS, TYPE A		EACH	4	4
78201000	TERMINAL MARKER - DIRECT APPLIED		EACH	1	1
78300100	PAVEMENT MARKING REMOVAL		SQ FT	500	500
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		EACH	68	68
X4403800	MEDIAN SURFACE REMOVAL		SQ FT	16411	16411
X6021065	INLETS, TYPE G-1, (SPECIAL)		EACH	2	2
X6060097	CLASS SI CONCRETE (OUTLET), SPECIAL		CU YD	9.2	9.2
X6640300	CHAIN LINK FENCE REMOVAL		FOOT	1780	1780
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)		L SUM	1	1
X7015005	CHANGEABLE MESSAGE SIGN		CAL DA	14	14
Z0007120	WELDED WIRE FABRIC 6X6		SQ YD	39	39
Z0013798	CONSTRUCTION LAYOUT		L SUM	1	1
Z0062456	TEMPORARY PAVEMENT		SQ YD	834	834
+ Z0076600	TRAINEES		HOOR	1,000	1,000

X SPECIALTY ITEMS + 0042

FILE NAME = D468A30-sht-plan.dgn	USER NAME = cousinjs	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 318	SECTION (72-6)R	COUNTY PEORIA	TOTAL SHEETS 117	SHEET NO. 9
PLOT SCALE = 1/8" = 100'	CHECKED -	REVISED -	CONTRACT NO. 68A30							
PLOT DATE = 3/19/2012	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							