

SCHEDULES OF QUANTITIES

SCHEDULE OF EARTHWORK QUANTITIES

LOCATION	EARTH EXCAVATION (CUT) CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE CU YD	EMBANKMENT (FILL) CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD	FURNISH EXCAVATION CU YD
ROUTE: I-74					
STA. 453+00 TO STA. 459+00	6	4.5	692	-687.5	687.5
ROUTE: US-51 (SOUTH BOUND)					
STA. 38+16 TO STA. 40+00	0	0	2	-2	2
ROUTE: I-55 (SOUTH BOUND LEFT)					
STA. 616+98 TO STA. 620+58	0	0	23	-23	23
ROUTE: I-55 (NORTH BOUND RIGHT)					
STA. 612+98 TO STA. 616+45	0	0	19	-19	19
ROUTE: I-55 (NORTH BOUND LEFT)					
STA. 613+70 TO STA. 616+39	0	0	30	-30	30
TOTAL	6	4.5	766	-761.5	761.5
USE	10				765

*NOTE: SHRINKAGE FACTOR IS 25%

LANDSCAPING SCHEDULE

	STATION	TO	STATION	AREA (ACRE)	SEEDING CLASS 2A (ACRE)	NITROGEN FERTILIZER (POUNDS)	PHOSPHORUS FERTILIZER (POUNDS)	POTASSIUM FERTILIZER (POUNDS)	MULCH METHOD 2 (ACRE)
I-55	NB LT 613+70.00		NB LT 614+00.00	0.01	0.01	0.9	0.9	0.9	0.01
	NB LT 614+00.00		NB LT 615+00.00	0.03	0.03	2.7	2.7	2.7	0.03
	NB LT 615+00.00		NB LT 616+39.00	0.03	0.03	2.7	2.7	2.7	0.03
	NB RT 612+98.00		NB RT 614+00.00	0.02	0.02	1.8	1.8	1.8	0.02
	NB RT 614+00.00		NB RT 615+00.00	0.02	0.02	1.8	1.8	1.8	0.02
	NB RT 615+00.00		NB RT 616+45.00	0.03	0.03	2.7	2.7	2.7	0.03
	SB LT 616+98.00		SB LT 618+00.00	0.02	0.02	1.8	1.8	1.8	0.02
	SB LT 618+00.00		SB LT 619+00.00	0.02	0.02	1.8	1.8	1.8	0.02
	SB LT 619+00.00		SB LT 620+58.00	0.04	0.04	3.6	3.6	3.6	0.04
	US-51	SB RT 38+16.00		SB RT 40+00.00	0.01	0.01	0.9	0.9	0.9
I-74	453+17.05		458+07.23	0.58	0.58	52.2	52.2	52.2	0.58
			TOTAL =	0.81	0.81	72.9	72.9	72.9	0.81
			USE =	1.0	1.0	90.0	90.0	90.0	1.0