



COMMUNICATIONS VAULT
1.0 EACH

UNDRGRD C MD
85 FT.

UNDRGRD C MD
34 FT. (PUSHED) UNDER DRIVEWAY

UNDRGRD C MD
332 FT.

UNDRGRD C MD
348 FT.

UNDRGRD C MD
80 FT. (PUSHED)
UNDER STRUCTURE
AND WATERWAY

UNDRGRD C MD
59 FT. (PUSHED)
UNDER DRIVEWAY

UNDRGRD C MD
626 FT.

Do Rd 1200 E

67

© 2011 Google
Image McDonough County GIS Consortium

Google earth

40°36'22.42" N 90°40'24.41" W elev 740 ft

Eye alt 2794 ft

SCHEDULE OF QUANTITIES		
ITS FIBER (US 67 FROM MACOMB TO MONMOUTH) - SHEET 32		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1564.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1614.0
COMMUNICATIONS VAULT	EACH	1.0

Imagery Date: 3/31/2010 1998

FILE NAME =	USER NAME = ke5thbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68B03 - D4 Fiber Project Sheets 1-109 (Macomb to Monmouth) - Final	DRAWN2.dgn	CHECKED -	REVISED -
	PLOT SCALE = 171.6216' / in.	DATE -	REVISED -
	PLOT DATE = 4/23/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
US 67 (FROM MACOMB TO MONMOUTH) CONTINUED

SCALE: SHEET NO. 32 OF 106 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	35
CONTRACT NO. 68B03				
ILLINOIS FED. AID PROJECT				