



COMMUNICATIONS VAULT  
1.0 EACH

UNDRGRD C MD  
228 FT.

UNDRGRD C MD  
505 FT.

UNDRGRD C MD  
57 FT. (PUSHED)  
UNDER DRAINAGE STRUCTURE

UNDRGRD C MD  
832 FT.

67

© 2011 Google  
Image McDonough County GIS Consortium

Google earth

40°37'38.79" N 90°40'24.13" W elev 769 ft

Eye alt 2794 ft

SCHEDULE OF QUANTITIES		
ITS FIBER (US 67 FROM MACOMB TO MONMOUTH) - SHEET 37		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1622.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1672.0
COMMUNICATIONS VAULT	EACH	1.0

Imagery Date: 3/31/2010 1998

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68B03 - D4 Fiber Project Sheets 1-109 (Macomb to Monmouth) - Final	DRAWN2.dgn	CHECKED -	REVISED -
	PLOT SCALE = 171.6216 ' / in.	DATE -	REVISED -
	PLOT DATE = 4/23/2012		

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT  
US 67 (FROM MACOMB TO MONMOUTH) CONTINUED

SCALE: SHEET NO. 37 OF 106 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	40
CONTRACT NO. 68B03			ILLINOIS FED. AID PROJECT	