



UNDRGRD C MD
1499 FT.

60th St

SCHEDULE OF QUANTITIES		
ITS FIBER (US 67 FROM MACOMB TO MONMOUTH) - SHEET 47		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1499.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1499.0

© 2011 Google

Image USDA Farm Service Agency

Google earth

Imagery Date: 6/27/2009 1998

40°40'08.90"N 90°40'23.40"W elev 750 ft

Eye alt 2794 ft

FILE NAME = c:\notes\erics plans\68B03 - D4 Fiber Project Sheets 1-109 (Macomb to Monmouth) - Final.dwg

USER NAME = keithbr	DESIGNED -	REVISED -
PROJECT SHEETS 1-109 (MACOMB TO MONMOUTH) - FINAL.DWG	CHECKED -	REVISED -
PLOT SCALE = 171.6216' / in.	DATE -	REVISED -
PLOT DATE = 4/23/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
US 67 (FROM MACOMB TO MONMOUTH) CONTINUED
SCALE: SHEET NO. 47 OF 106 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	50
CONTRACT NO. 68B03			ILLINOIS FED. AID PROJECT	