



UNDRGRD C MD
770 FT.

UNDRGRD C MD
803 FT. (PUSHED)
UNDER ROADWAY

UNDRGRD C MD
831 FT.

SCHEDULE OF QUANTITIES		
ITS FIBER (US 34 FROM MONMOUTH TO GALESBURG) - SHEET 10		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	2404.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	2404.0

©2011 Google

Image USDA Farm Service Agency

Google earth

Imagery Date: 6/27/2009 1998

40°55'32.08" N 90°35'36.31" W elev 741 ft

Eye alt 2794 ft

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68B03 - D4 Fiber Project Sheets 110-157 (Monmouth to Galesburg)	DRAWN 19-12.dgn	CHECKED -	REVISED -
	PLOT SCALE = 164.7568' / in.	DATE -	REVISED -
	PLOT DATE = 4/23/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
US 34 (FROM MONMOUTH TO GALESBURG) CONTINUED

SCALE: SHEET NO. 10 OF 48 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	119
CONTRACT NO. 68B03			ILLINOIS FED. AID PROJECT	