



WARREN COUNTY
RURAL

KNOX COUNTY
URBAN

UNDRGRD C MD
1344 FT.

UNDRGRD C MD
605 FT.

UNDRGRD C MD
116 FT. (PUSHED)
UNDER STRUCTURE

UNDRGRD C MD
474 FT.

COMMUNICATION VAULT
1.0 EACH

180TH ST (COUNTY LINE RD)

34

SCHEDULE OF QUANTITIES		
ITS FIBER (US 34 FROM MONMOUTH TO GALESBURG) - SHEET 28		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	2539.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	2589.0
COMMUNICATIONS VAULT	EACH	1.0

Imagery Date: 6/27/2009 1998

© 2011 Google

Image USDA Farm Service Agency

RURAL
WARREN COUNTY

URBAN
KNOX COUNTY

Google earth
WARREN

Eye alt 2793 ft

40°55'19.47" N 90°26'51.29" W elev 724 ft

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68B03 - D4 Fiber Project Sheets 110-157 (Monmouth to Galesburg)	DRAWN 19-12.dgn	CHECKED -	REVISED -
	PLOT SCALE = 164.7568' / in.	DATE -	REVISED -
	PLOT DATE = 4/23/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
US 34 (FROM MONMOUTH TO GALESBURG) CONTINUED

SCALE: SHEET NO. 28 OF 48 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	137
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68B03	