



US 34

I-74

UNDRGRD C MD
465 FT.

UNDRGRD C MD
112 FT. (PUSHED)
UNDER ROADWAY

UNDRGRD C MD
454 FT.

COMMUNICATIONS VAULT
1.0 EACH

UNDRGRD C MD
130.0 FT (PUSHED) UNDER ROADWAY

RURAL

RURAL

URBAN

URBAN

SCHEDULE OF QUANTITIES		
ITS FIBER (GALESBURG TO WOODHULL) - SHEET 1		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1159.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1209.0
COMMUNICATIONS VAULT	EACH	1.0

©2011 Google

Image USDA Farm Service Agency

Google earth

Imagery Date: 6/27/2009 1998

40°59'02.69"N 90°20'09.74"W elev 814 ft

Eye alt 2793 ft

FILE NAME =	USER NAME = howalder	DESIGNED -	REVISED -
S:\GEN\DRFT\ITS Fiber Project\68B03\68B03 - D4 Fiber Project Sheets 158-206 (Galesburg to Woodhull) - Final 4-19-12.dgn		DRAWN -	REVISED -
	PLOT SCALE = 163.0405' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/23/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 (FROM GALESBURG TO WOODHULL)

SCALE: SHEET NO. 1 OF 49 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	158
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68B03	