



UNDRGRD C MD

21 FT.

COMMUNICATIONS VAULT

1.0 EACH

UNDRGRD C MD

1485 FT.

THERE ARE DRAINAGE STRUCTURES THAT ARE NOT SHOWN ON THIS SHEET. THE CONTRACTOR SHOULD BE ABLE TO TRENCH AROUND THESE STRUCTURES, HOWEVER, THIS INFORMATION IS BEING PROVIDED FOR REFERENCE ONLY AND THE CONTRACTOR SHALL VERIFY ALL FIELD CONDITIONS PRIOR TO BIDDING.

SCHEDULE OF QUANTITIES		
ITS FIBER (GALESBURG TO WOODHULL) - SHEET 3		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1544.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1594.0
COMMUNICATIONS VAULT	EACH	1.0



40°59'24.26" N 90°20'08.63" W elev 811 ft

© 2011 Google
Image © 2011 GeoEye

Google earth

Eye alt 2793 ft

FILE NAME =	USER NAME = keithbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68803 - D4 Fiber Project Sheets 158-206 (Galesburg to Woodhull) -		DRAWN 9-12.dgn	REVISED -
	PLOT SCALE = 163.0405' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/24/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 (FROM GALESBURG TO WOODHULL) CONTINUED
SCALE: SHEET NO. 3 OF 49 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	160
CONTRACT NO. 68B03			ILLINOIS FED. AID PROJECT	