



UNDRGRD C MD  
593 FT.

UNDRGRD C MD  
67 FT. (PUSHED)

UNDRGRD C MD  
798 FT.

COMMUNICATIONS VAULT  
1.0 EACH

UNDRGRD C MD  
123 FT.

SCHEDULE OF QUANTITIES		
ITS FIBER (GALESBURG TO WOODHULL) - SHEET 48		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1581.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1631.0
COMMUNICATIONS VAULT	EACH	1.0

Imagery Date: 9/12/2011 1993

41°10'26.06" N 90°19'55.10" W elev 819 ft

Eye alt 2791 ft

© 2011 Google

Google earth

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68B03 - D4 Fiber Project Sheets 158-206 (Galesburg to Woodhull) -		DRAWN 9-12.dgn	REVISED -
	PLOT SCALE = 163.0405' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/24/2012	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT  
I-74 (FROM GALESBURG TO WOODHULL) CONTINUED

SCALE: SHEET NO. 48 OF 49 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	205
CONTRACT NO. 68B03			ILLINOIS FED. AID PROJECT	