



UNDRGRD C MD

286 FT.

COMMUNICATIONS VAULT

1.0 EACH

I-74

UNDRGRD C MD

1040 FT.

UNDRGRD C MD

250 FT. (PUSHED)
UNDER ROADWAY

SCHEDULE OF QUANTITIES		
ITS FIBER (WOODHULL TO MOLINE) - SHEET 19		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1576.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1626.0
COMMUNICATIONS VAULT	EACH	1.0

Imagery Date: 9/12/2011 1993

41°15'07.92" N 90°19'44.72" W elev 732 ft

Eye alt 2791 ft

© 2011 Google

N. 700TH AVE. Google earth

FILE NAME =	USER NAME = keithbr	DESIGNED -	REVISED -
c:\notes\68b04 fiber plans\68b04\68B04	- Woodhull to Moline (1-95) - Final 4-30-12.dgn	DRAWN -	REVISED -
	PLOT SCALE = 164.7568' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/1/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 (FROM WOODHULL TO MOLINE) CONTINUED

SCALE: SHEET NO. 19 OF 62 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2013	HENRY/ROCK ISL	96	22
CONTRACT NO. 68B04				
ILLINOIS FED. AID PROJECT				